

# You'll be happy with a Fretwork Outfit!

A delightful and useful hobby for every boy

You can make spare pocket money at it

Hobbies supply Outfits complete from 4/- to 57/6

Don't buy cheap or inferior foreign goods

Free designs are given every week with Hobbies


Write for Free Lists and Booklet to Dept. 96,

### HOBBIES LTD., DEREHAM, NORFOLK

65, New Oxford St., London, W.C.; 147, Bishopsgate, London, E.C.; 79, Walworth Road, London, S.E.; 326, Argyle Street, Glasgow; 10a, Piccadilly, Manchester; 9a, High Street, Birmingham; 15, County Arcade, Leeds; 11, Bridge Street, Southampton; 68, London Road, Brighton, and agents in every town.


The No. 2½
OUTFIT
COMPLETE
Price - 6/6

Postage 6d. extra.



On Edged Card, 16ins. by 12ins.

Contains a 12in. Handframe, Archimedean Drill with 3 Bits, Cutting Table with Iron Cramp, Six Sawblades, Sandpaper Block, and Design.



EDITORIAL OFFICE
Binns Road,
LIVERPOOL



PUBLISHED

IN THE INTERESTS

OF BOYS



ONLY six weeks more in which to try to win one of the many valuable trophies offered in the £250 Championship Contest! For some time past

The Great Championship Contest Meccano boys the world over have been busily engaged in perfecting, improving, and finishing-off their models

before finally sending in their entries for the great competition. For some years past I have followed the results of the Model-Building Competitions and have each year closely inspected the winning entries. One thing has been very forcibly impressed on me, and that is that the whole secret of success in these competitions is contained in the one word "originality."

To win a prize don't copy or improve on a model already in the Meccano Instruction Manuals. You should remember that

How to Win the judges are all experienced model builders themselves, and that they know the models in the Manuals

as well as you know how often the "M.M." is published! What the judges look for is some movement or some original model they have never seen made in Meccano before. They look for some model that will attract their attention. Your model need not be a complicated piece of mechanism, but it should be attractive because of its originality. It should be so attractive indeed, as to make the judges feel they must just drop every other job and set to work "this very minute" to build your model for themselves. You will never make them do this if you submit some model that has been copied from the Instruction Manuals.

This year the Competition is being run on new and original lines. Championship Cups and Medals are being awarded to

Meccano countries or groups of countries. These countries are divided

into sections, depending on the age of the competitor, so that every one is treated fairly and the models of boys of the same ages are judged together. The winner of each Championship Cup will hold the

title of "Meccano Champion" for his particular group for twelve months. The award of these cups will be closely followed by all Meccano boys and everyone will be interested to learn who are the lucky recipients.

Every year entries for this great competition come in thousands from all parts of the world. In one sense, therefore, the establishment of the competition on the new lines makes it of a distinctly international character. More especially is this the case, however, with the special gold medal that is to be awarded for the best model in the entire competition. I cannot help wondering to which country this medal will be awarded. I sincerely hope that it will be won by a British boy, although I know that if this is the case British Meccano boys will require to "put on their thinking caps," for they have very serious rivals in the boys of France and America, not to mention Italy and Spain! So now "get busy" boys and see that your entries are despatched well before 15th April. (Full particulars of this contest on page 79).

### Next Month:

FAMOUS ENGINEERS:—
George Stephenson (Part III.)

WONDERFUL NEW COALER

ELECTRICITY: More Experiments with Static Electricity

STAMP COLLECTING:—
Papers and How to Identify Them

INTO THE LAND OF FUN:—
New Parts and their Uses

MILLIONS OF UNDERGROUND
TRAVELLERS:—
Wonders of London's Tube Railways

WHAT BROADCASTING MEANS:—

How a Transmitting Station "Works"

COMPETITIONS, GUILD NEWS, CLUB
NOTES, PUZZLES, and other regular features

The suggestion has been made hundreds of times that we should supply a Meccano jersey, and I am now able to say that

Meccano

the necessary arrangements to make this practicable have been made with the Jaegar

Company. I have seen samples of these jerseys and must say they are of very pleasing appearance. They are supplied in a range of colours, and the design has been approved by Mr. Hornby himself. The name of the Jaeger Co. is a sufficient guarantee of their quality. Meccano boys will now be more easily recognised than ever, and I shall keep my eyes open during my travels for any boy wearing these jerseys! Full details will be found in our advertisement pages. (See page 70).

I think I have previously mentioned in this column that I am always pleased to receive suggestions for articles or special

Improving the "M.M."

features for the "M.M."
Our circulation has been increasing by


leaps and bounds, and if this is any guide it would seem that my ideas as to what Meccano boys want in their paper are on right lines. Of course, it is difficult to please everyone, and out of 40,000 regular readers there are sure to be a few complaints, but I welcome complaints as well as suggestions, for they indicate what readers do not want! Among the many suggestions made recently have been insistent demands for pages dealing with Nature Study, Cycling, Photography, and Railway topics, and I should very much like to hear from those readers who are in favour (or against) such features. A postcard will serve the purpose, and if you are able to suggest any other articles that you think will be of interest during the summer months, mention them at the same time. Our Puzzles have been well received, and we shall continue these, and also the stamp page, as a large number of readers have expressed their satisfaction of this feature. We hope shortly to commence a serial stamp article of a novel character. This will take the form of a tour round the world, as illustrated by postage stamps. Special attention will be given to the great engineering structures as depicted on stamps. Many other interesting articles are being prepared and will be announced in due course. Articles on "Electricity" have been promised for some time, and I am pleased to be able to print the first of the series this month. The article describes how readers may experiment without danger with this great and mysterious force.

### How to Obtain the "M.M."

The "Meccano Magazine" may be ordered from your Meccano dealer, or from any newsagent or bookseller, price 2d. If you are not able to obtain the "M.M." from these sources it may be obtained direct from this office, post free, 6 issues 1/6, 12 issues 3/-.

The next number of the "M.M." will be ready on 1st April. As we print only sufficient copies to supply orders received, you should place a regular order with your dealer or newsagent, or direct with this office, to avoid disappointment.

"Meccano Magazine,"
Binns Road, Liverpool



In our article last month we described the construction and purpose of steam navvies. In these columns we deal with another type of excavator, called the Dragline.

The Dragline obtains its name from the fact that the bucket is dragged towards the machine on a flexible rope, instead of being mounted on an arm that pivots on a jib.

### Steam Navvies and Draglines

The single-bucket excavators previously described have three special features by which they may be classified. (1) They excavate above the level on which they stand (2) they dig away from the machine, and (3) they advance into the excavation as the work proceeds.

Draglines work in an exactly opposite manner, for they excavate below the level on which they stand; they work towards themselves, and they travel backwards when they have excavated all material within reach.

Draglines are used principally for drainage work, or where the ground is too wet to allow a steam navvy to stand. In certain parts of the Panama Canal Draglines were extensively used, and in conjunction with steam navvies they did the work of thousands of labourers, at a fraction of the cost.

### A Great Engineering Feat

In such circumstances these mechanical devices are of inestimable value to the engineer. Apart altogether from the fact

that their upkeep is nothing like the amount that would be required in wages if men were employed, they eliminate the difficult question of housing and feeding.

The zone of the country through which the Panama Canal passes is uninhabited, and the cutting of the canal necessitated the erection of large numbers of shelters and temporary houses for the workmen.

In our last number we gave an account of steam navvies—mechanical appliances that have made possible many engineering feats. We are now able to print an article describing another type of these same remarkable machines that has played its part in the advancement of civilisation.

Even when every conceivable form of laboursaving device was used, it was still necessary to employ over 60,000 men. These men, with their wives and families, had to be housed and fed in what was practically a desert area. This itself was a very big task, but if it had not been for the employment of mechanical devices such as steam navvies and Draglines, the number of labourers required would have been so enormous as to have made it impossible to accommodate them. It is more than probable that without these mechanical devices the Canal would never have been constructed at all—at any rate it is certain that the completion of this great work would have been delayed for very many years.

### Details of the Dragline

A Dragline is very similar in construction to a steam navvy. Indeed, the latter may be so designed that it may be converted into a Dragline if desired, simply by fitting a different jib and special bucket, and adding another winding-drum to the machinery.

There are two drums—one for the

digging rope and the other for lifting the bucket out of the excavation, regulating the depth of cut, and allowing the bucket to swing back for discharging and for another cut. In the steam navvy the digging rope passes over a pulley at the top of the jib, but in the Dragline the digging rope passes out at the front of the machine, close to the foot of the jib, and is con-

nected to the bucket. A hoisting rope, which takes the weight of the bucket and its load, runs over the head of the jib and is attached to the bucket.

### The Lattice-Girder Jib


The jib of a Dragline is a lattice-girder and is of lighter design than the jib of the steam navvy. This is made possible by the fact that in a Dragline the jib takes only the load due to the lifting rope, and this with the slewing motion, is its only stress. In the steam navvy, however, the jib takes the stress not only from the digging rope but also bears the whole of the excavating stresses from the bucket arms, with their attendant slewing and digging stresses. In the Dragline the stresses at the head of the jib are

## Where Do Old Guns Go?

to discarded naval guns? And why should we discard them? Every nation with a Navy strives to build guns of greater power than those of its neighbours, and in this age of continual progress naval guns soon become obsolete. The result is that when a new gun is designed, the older guns become useless and are consequently demolished. This process is commonly known as "scrapping," and the term is also applied to ships, buildings, etc., as well as to guns.

When a gun is condemned it is sold to some firm of scrap-metal dealers, who offer the highest price for it. The name of the firm is painted on the gun, together with the word "Sold." The gun shown in our illustration was purchased by a firm in Wales whose name appears in white near the rifling of the barrel.

The gun is then removed to the scrapyard by the large gantry crane (seen in the distance in our photograph) and electric drills or powerful hydraulic tools split open the outer steel jacket along the length of the barrel. As this outer covering is released and lifted clear, thousands of lengths of steel wire fly out. In the case illustrated these have assumed the curious appearance of a sheaf of corn. This wire is wound around the barrel to take the heavy shock of the gun when it



Photograph by]

kind criticisms.

[G. Knapman

Cutting the Wire wound around a Naval Gun

is fired, and to prevent the barrel from splitting up. The wire also is treated as scrap, and every part of the gun is melted down and the metal is, perhaps, used again in guns of a later type.

In some future number of the "M.M." we hope to describe how large guns are made, and also to tell something of the making of armour plate and of the great machines used in the processes.

### The Heaviest Dragline in the World—(cont.)

considerably less than in the case of the steam navvy and so the jib may be made longer. This also is an advantage in this class of work, for it enables the bucket to be thrown out further and to take a deeper and wider cut.

The angle at which a Dragline jib is inclined is much flatter than that of the steam navvy, because a large working radius is very useful and working height is not a necessary consideration. Draglines are usually fitted with derricking gear for altering the working radius. The variations possible in the angle of the jib are generally from 25° to 40° from the horizontal in the case of a Dragline, and from 45° to 60° in a steam navvy.

### £5 for a Meccano Model

Messrs. Ruston & Hornsby Ltd., of Lincoln, who are famous as builders of Draglines and steam navvies, have recently built a very large Dragline, which is the subject of the illustration at the head of page 58. We shall continue this descriptive article in our next issue, and we advise all our readers to follow the details very closely, for Messrs. Ruston & Hornsby Ltd. are anxious to see whether any Meccano boy is sufficiently clever to build a working model of this great Dragline. connection we are arranging a competition, full particulars of which will be announced in our next issue. Messrs. Ruston & Hornsby Ltd. are offering a prize of £5, and there will also be other prizes to be won in this connection.

(To be continued)



In these columns the Editor replies to letters from his readers, from whom he is always pleased to hear. He receives hundreds of letters each day, but only those that deal with matters of general interest can be dealt with here. Correspondents will help the Editor if they will write neatly in ink and on one side of the paper only.

J. Rayburn (Royton).—

"Now for the start—we're off again,
Nothing so safe as a Hornby Train.
Round the bend—oh! isn't it grand?
Now we've arrived in Meccanoland."

Your complete poem is very good, and we are sorry we can only print one verse. Many thanks for your

A. Banister (Stoke Poges).—It was good to hear from you again, and to know that you are following the Meccano hobby and the "M.M." so closely. We sincerely trust that the necessary sum will be raised to restore the Stoke Poges Church Spire, made immortal in Gray's Elegy.

G. Harding (Highgate, N. 19).—We are pleased to know that our Stamp Column appeals to you so strongly. We will gladly reply to any queries on stamps.

J. Cooper (Glasgow).—Our Meccano boys are growing up into Meccano men all the time. We are glad to hear that your interest in the hobby is still keen. We wish you all success in your business career.

A. Knight (Chichester).—We are glad to welcome you back to the Editorial fold and to be able to send you the back numbers of the "M.M." that you missed. We strongly counsel you not to miss any of the coming issues, and as we now print only as many copies as are actually ordered, it is unlikely that we shall be able to supply back numbers in the future.

H. Thompson (Scotstoun).—The increase in size of the "M.M." is not intended to make you suffer from "fits of joy," Henry! Thanks for your congratulations and for print of the proposed new road-bridge across the Forth. The Stamp Editor will reply to your last query.

R. Gay (Christchurch, N.Z.).—Many thanks for your interesting description of the Hydro-Electric Power Station at Lake Coleridge. We are always glad to hear from you and we wish you success in the "Star" competition.

A. F. Battersby (Mitcham).—It is always a pleasure to hear from older Meccano enthusiasts, and we gather from your letter that you derive as much pleasure from model building as your boys. Your criticisms are all sound and have been noted. We shall be glad to see you on your next visit to Liverpool.

L. H. W. Wright (South Shields).—Of course we know that it is dangerous to go to church when the organist is drowning the choir, and when the canon fires away at the congregation from the pulpit, but no Meccano boy would seriously make this an excuse for staying away from church.

W. H. Robson (Backworth).—We think that stories "to make the hair stand on end" would be out of place in the "M.M." Your suggestion for a nature column is on much sounder lines, and we have this under careful consideration. When we do decide to introduce this feature it will be on distinctly novel and attractive lines.

Aubrey Nairn (Perth, W. Australia).—We quite agree with the sentiments expressed in your verses, Aubrey, but we think you must improve your rhyming if your efforts are to see print. We do not think your suggestion re circular strip is practicable.

A. Bentley (Padiham).—The verses you have written to illustrate the humorous sketch on the "Fireside Fun" page in our Christmas number are quite good. We were sorry to hear that you have been ill in bed, and we hope that you are now well on the way to recovery.

G. H. Mawson (Leeds).—We were glad you told us that the answer to your riddle "Can you spell hungry horse in four letters?" is "M.T.G.G." as otherwise this issue of the "M.M." might never have been published! Thank you for your good wishes, which we heartily reciprocate.

C. Roberts (Liverpool).—The interest expressed in our new puzzle feature has been very considerable, and we shall certainly continue this page. You should have no great difficulty in solving most of the puzzles in view of your thorough acquaintance with Algebra. You evidently find this subject useful, and we feel sure that if you maintain your interest you will find Algebra even more useful in later life.



## II. GEORGE STEPHENSON, the Man Who Gave Railways to the World.

the first instalment of this article, which appeared in our January issue, we described Stephenson's early days when he was employed at Killingworth Colliery. We also told how he came to build his first locomotive and how it was proposed to construct a railway between Stockton and Darlington.

Stephenson persuaded the directors of the new railway to use locomotives instead of employing horses to draw the wagons or hauling them by fixed engines, as had also been suggested. His confidence in the future of the locomotive was unbounded and on one occasion at this time he said, speaking to his son Robert, "I think you will live to see the day when railways will come to supersede almost all other methods of conveyance in this country-

when mail coaches will go by railway, and railroads will become the great highway for the King and all his subjects. The time is coming when it will be cheaper for a working man to travel on a railway than to walk on foot. There are great and almost insurmountable difficulties that will have to be encountered, but what I have said will come to pass, as sure as you live." What a remarkable prophecy this was! Today the complicated and extensive railway systems of the world far outdistance even these intelligent anticipations of Stephenson.

### An Important Discovery

In 1823 the construction of the Stockton and Dar-

lington Railway commenced, and Stephenson was appointed the Company's Engineer at a salary of £300 per annum. He established a locomotive works at Newcastle at the same time, and here three locomotives were built for the Stockton and Darlington Railway, embodying Stephenson's latest discovery, the steamblast. This was one of the famous engineer's greatest triumphs, and to it he owed a considerable measure of his ultimate success. It is of such importance that we shall stop to consider it in detail.

First let us explain that the cost of running Stephenson's original engines was about the same as if horses had been used. Their speed also was about that of the walking pace of a horse, so that really there had been little in favour of the

colliery adopting the steam engine instead of horses for haulage purposes. It has been said, indeed, that the fate of the locomotive was at this stage trembling in the balance, and it is quite possible that it might have been condemned as useless had it not been for the invention of the steam-blast.

In the early engines the exhaust steam from the cylinders had been allowed to escape directly into the air. It issued from the exhaust ports with a hissing blast and frightened all horses and cattle within earshot—not to mention pedestrians! In fact, so much annoyance had been caused by the exhaust steam that a neighbouring squire threatened to commence an action against the colliery

of overcoming this difficulty was to increase the intensity of the fire in the furnace. In 1815 Trevethick, another inventor, had taken out a patent for a method of urging the fire by fanners, similar to those used on a winnowing machine, but this solution to the difficulty had not been wholly satisfactory, apart from the fact that additional mechanism was

in sufficient quantity to keep the engine

constantly working. The only method

required to work the appliance. On the other hand, Stephenson's blast was entirely successful—so much so, indeed, that it more than doubled the power of the engine. This was a splendid achievement, for it must be remembered that it was attained without any increase in

weight, which Trevethick's invention necessitated.

The addition of the steam-blast marked the turning-point of a critical stage in the history of the locomotive, and consequently in Stephenson's life. Even had the locomotive survived this critical period without the blast, the high speeds obtained later and the multi-tube boiler could not have been developed without it. The steam-blast is used extensively to-day, as anyone may see, when a loco is getting up steam or running at high speed. We have all noticed the steam coming from the smoke stack and the force with which the smoke expelled—just as it was in Stephenson's time.



Photograph by]

[" Newcastle Chronicle" "High Street House," Wylam-on-Tyne, the humble cottage in which George Stephenson, one of the world's greatest engineers, was born

on which Stephenson's locos were used, if the nuisance did not cease!

### The Steam-Blast

Stephenson had already noticed that the steam issued from the exhaust with a greater velocity than that with which smoke issued from the chimney of the loco. It occurred to him that if the exhaust steam were conducted to the chimney by a pipe and allowed to escape in a vertical direction, it would cause the smoke from the furnace to travel at an increased velocity. This in turn would cause a greater draught in the furnace and so enable it to burn more coal and give greater heat. This had been desired for some time, for it had been found difficult to produce steam

### A Famous Loco

Having developed the steam-blast on his Killingworth engines, Stephenson rightly decided to fit it to the locos he made for the Stockton and Darlington Railway. These locos each weighed about eight tons, and they were capable of speeds of up to 16 miles per hour. The first was named the "Locomotion" and is now to be seen on the platform of Darlington Railway Station. In this engine a tube through the boiler served as a large flue, by which heated air passed directly from the fire-brick furnace at one end, to the chimney at the other. The steam-blast entered the chimney and quickened combustion so that the heat was sometimes so great as to cause the chimney to become almost red-hot!



From an old]

The Opening of the Stockton and Darlington Railway

[engraving

After many months of work the Stockton and Darlington Railway was at last ready to be opened. The ceremony was performed on the 27th September, 1825, and we may easily imagine how anxious Stephenson was as to what would be the issue of his great experiment. As the great day approached the excitement grew more and more intense, but it seems that Stephenson's confidence in the success of the railway was unshaken.

of Middlesbrough and the prosperity of

It is interesting to find that although the Stockton and Darlington Railway was originally constructed for the carriage of coals from the Durham mines for sale at the stations along the line, this work proved to be only a small portion of the

### A Notable Ceremony

There had been considerable opposition to the construction of the Stockton and Darlington Railway, and when the line was opened great crowds of people came from all parts of the country to witness the ceremony. Many threats had been uttered against the Company by various people, who declared they would prevent the line from being worked. Probably quite as many people attended the opening ceremony in the hope of seeing the new invention fail, or the engine blow up, as those who went to cheer.


Those who anticipated a great disaster were disappointed, however, for nothing of the kind happened. Instead, the opening was a great success. Stephenson himself drove the engine of the first train, consisting of six wagons loaded with coals and flour. After these came a passenger coach filled with directors and their friends, and twenty-one wagons fitted with seats. Lastly there were six wagons loaded with coals, making a train of thirty-five vehicles in all.

A witness of the scene quaintly described how "the signal being given, the engine started off with this immense train of coaches, and such was its velocity that in some parts the speed was frequently twelve miles an hour." When the train reached Stockton there were about 600 persons either in the train or hanging on to the wagons, each anxious to be amongst those able to claim having ridden in the first train!

The regular working of the line commenced immediately after the opening, and an enormous amount of coal was shipped from Stockton and Middlesbrough by means of the railway. At that time Middlesbrough as a town was unknown, for where this large and prosperous town now stands there were only a few cottages. The railway soon changed this, however, and it may be truly said that the town

the surrounding district were the direct outcome of the invention of the steam-

traffic that came to the railway. Even



["Engineering for Boys"

The famous "Locomotion," now to be seen on the platform at Darlington (Bank Top) Railway Station

selves surprised at the amount of new traffic that came to them, principally the haulage of coals to the seaports for export to London and elsewhere. When the bill for the establishment of the railway was before Parliament, the Earl of Durham had succeeded in having a clause insert-

ed limiting the railway comcharge for carrying coal to one half - penny per ton per mile. The object of this was to protect the Earl's own trade for coal that he himself exported from other ports. Everyoneincluding

the projectors of the railway were them-

From an okl]

congraving The Westmoor Colliery, Killingworth, Northumberland, where Stephenson was at one time employed as brakesman

the directors of the railway-believed that this very low rate would make it impossible for the company to carry coals to the ports, but when the railway opened, the shipment of coal to the ports at the half-penny rate was enormous. Instead of there being no traffic as the railway company had anticipated, this did, in fact, form the main traffic of the railway.

In a similar manner, passenger traffic, which had not been thought of seriously in the original estimates, became considerable. The running of the trains between Stockton and Darlington brought many new businesses into existence and an increasing traffic in passengers sprang up.

Shortly before the railway was opened, Stephenson was requested to build a railway coach. This was the first railway carriage in existence, and it was not unlike a bathing machine or hut on wheels! There was a row of seats on each side, with a long deal table in the centre and a door at the back. This coach, which Stephenson appropriately named the " Experiment," was the forerunner of our splendid Pullman coaches of to-day. At first the "Experiment" was drawn by a

horse and performed the journey between the two towns—a distance of 12 miles—in about two hours. Soon, however, this coach was found to be too heavy and uncomfortable, and its place was taken by better carriages which were, in fact, made from old stage coach bodies mounted on under-frames fitted with flanged wheels! In the "Experiment" the fare was 1/- and there was no distinction of class, but in the new carriages there were inside and outside passengers who were charged different fares, and so first and second - class distinction commenced.

 $NEXT\ INSTALMENT:-$ 

Stephenson's Greatest Triumph: The Conquest of Chat Moss

# MECCANO ACCESSORY OUTFITS

# Make Your Outfit Bigger and Better

Once a boy has commenced to build with Meccano, he desires to build larger and more ambitious models. He may do so by adding an Accessory Outfit to his existing set, thereby greatly increasing its scope. The particulars below show how a boy who commences with one of the earlier Outfits may build up his equipment by easy stages, until he is the proud owner of a No. 7 Outfit.

### PRICE LIST

Complete Outfits

No.	00				3/6
No.	0				5/-
No.	1				8/6
No.	2				15/-
No.	3				22/6
No.	4				40/-
No.	<b>5</b> (I	n we	ll-mad	e carton)	55/-

No. 5 (In superior oak cabinet with lock & key) 85/-

No. 6 (In well-made carton) 105/

No. 6 (In superior oak cabinet with lock & key) 140/-

No. 7 (In superior oak cabi- 370/- net with lock & key)



### PRICE LIST

Accessory Outfits

No. (	)0a		 1/6
No.	0a		 4/-
No.	la		 7/6
No.	2a		 8/6
No.	3a		 18/6
No.	la		 15/-
No. 5	ja	(carton)	 50/-
No. 5	5a	(wood)	 80/-
No.	ia		 210/-

This illustration shows a No. 3a Outfit which converts a No. 3 into a No. 4 Outfit.

### No. 00a OUTFIT

Costs 1/6, and converts No. 00 into a No. 0 Outfit. With it an additional 27 models may be built, making a total of 70 models in all.

### No. 2a OUTFIT

Costs 8/6, and converts No. 2 into a No. 3 Outfit. With it an additional 43 models may be built, making a total of 206 models in all.

### No. 5a OUTFIT (Carton)

Costs 50/-, and converts No. 5 into a No. 6 Outfit (carton). With it an additional 51 models may be built, making a total of 353 models in all.

### No. 0a OUTFIT

Costs 4/-, and converts No. 0 into a No. 1 Outfit. With it an additional 36 models may be built, making a total of 106 models in all.

### No. 3a OUTFIT

Costs 18/6, and converts No. 3 into a No. 4 Outfit. With it an additional 53 models may be built, making a total of 259 models in all.

### No. 5a OUTFIT (Wood)

Costs 80/-, and converts No. 5 into a No. 6 Outfit (wood). The parts are exactly the same as in the carton Outfit mentioned in the preceding panel, but the cabinet is in wood.

### No. 1a OUTFIT

Costs 7/6, and converts No. 1 into a No. 2 Outfit. With it an additional 57 models may be built, making a total of 163 models in all.

### No. 4a OUTFIT

Costs 15/-, and converts No. 4 into a No. 5 Outfit (carton). With it an additional 43 models may be built, making a total of 302 models in all.

### No. 6a OUTFIT

Costs 210/-, and converts No. 6 Outfit into a No. 7 Outfit (oak cabinet). This Outfit builds every one of the 393 models illustrated in the Complete Manual.


FROM ALL MECCANO DEALERS



Into the Land of Fun

by


"SPANNER"



Finding ideas for new models should not be a difficult matter for any bright boy, however, and after all, it is this inventive power—this touch of originality—that Meccano is able to cultivate in boys.

I remember that in my early Meccano days I was never particularly interested in copying models from the Manuals, after I had once learned how to build and how to use the parts correctly. I have always preferred to build in detail new movements for various mechanisms, and from these I have obtained any amount of enjoyment and satisfaction. When short of an idea my usual procedure was to go for a walk with the sole intention of finding something new to reproduce in Meccano. The first time I went out on one of these hunting expeditions I got no further than the garden gate. Regarding it critically it seemed to be quite a cumbersome arrangement. I thought I could improve upon it, so I went indoors and

It was quite a success and I was very proud of the special self-closing and locking device, which I exhibited to my parents and friends. I was never disappointed in my later rambles and always managed to find something new. Some of my happiest memories are of the days when I used to copy the bridges, carts, railway-stations, trams, 'buses and even top-hatted old gentlemen that I saw!




Model No. 446. Pantograph

And now for our monthly chat on the interesting models illustrated on this page. No. 434 (Cakewalk) is an old favourite of mine. Even though my dog "Lady" has grown into quite a big dog now, she will never forget her first (and only!) experience as a puppy on those treacherous platforms on which she was an unwilling passenger!

The model here illustrated is worked by hand, but I substituted a pulley wheel for the handle and drove the Cakewalk by a belt from an electric motor. In either case the results are equally good, however, and the model has the added charm of being very simple to construct.

The rocking platforms are built of braced girders, connected by 2½" end strips and pivotally bolted and lock-nutted to the other 2½" strips which form the rocking-links or mounting. These latter are bolted and lock-nutted to the angle girders beneath. The platforms themselves are made of stout cardboard and are secured to the 2½" end strips. They are rocked by means of the two 6" strips, each of which is connected to one rocking platform (only one is to be seen in the illustration). The other end of the strip is connected to a Triple-Throw Eccentric, fixed on a rod, to which is also secured a contrate wheel, driven by a pinion from




Model No. 452. Anti-Aircraft Gun

\* the hand-wheel. As the handle is turned, the platforms rock up and down on the supporting strips. The Eccentrics should be so arranged that the platforms rock in opposite directions.

By the way, the Triple-Throw Eccentric (No. 130) is not very well known to Meccano boys and the Editor tells me that he often has letters from readers enquiring how the part is to be used. I hope next month to describe some of the uses to which this and other recently-introduced parts may be applied.

A model of an entirely different character to the Cakewalk is No. 446, which goes by the high-sounding name of "Pantograph." In actual practice this is a device used by draughtsmen and artists for copying plans and designs, either on a reduced or an enlarged scale.

When constructed, the apparatus is fixed with a wood screw by the left hand corner to the table or board. The drawing to be copied is laid flat on the table as shown in the centre of the accompanying illustration. To make an enlarged reproduction of the original the point is traced around the outlines of the drawing. At the right-



Model No. 434. Cakewalk


hand corner there is a pencil or fountain pen, which exactly reproduces the original sketch, but on a larger

scale. With a little practice, and by taking the pencil in the fingers, very good results may be obtained. If a drawing reduced in size is desired, then the outline is traced with the pencil and point reversed—that is to say the pencil is placed in the central holder and the tracing point in the holder on the right. This arrangement reproduces the sketch on a smaller scale, the size of which depends on the position of the tracing point on the perforated strip.

A great deal of fun may be obtained from Model No. 452, Anti-Aircraft Gun, if used in conjunction with Model No. 423 Searchlight Tower (illustrated in the January "M.M.") These two models may be placed side by side or they may be mounted on a common base. Then when the electric lamp of the Searchlight is switched on, and the beam directed on to various objects in the room, the "man behind

the gun "should endeavour to follow the beam by manipulating the controls of the gun. These are ingeniously contrived to give almost any desired movement, as is the case in real anti-aircraft gunnery.

A 57-toothed wheel mounted on a pivot rod engages a worm, which is operated from the small hand-wheel. By turning this wheel the gun-barrel is raised or lowered. Two vertical strips form the framework for the pivot rod and are



Model No. 453. Tip Wagon

bolted to a 1½" pulley wheel, secured on a vertical rod. A 3" pulley wheel is also bolted to the rod and from the pulley wheel a framework is carried by reversed angle brackets. The rod with the framework is rotated by a hand-wheel, a pinion on the spindle of which engages a ¾" contrate wheel on the rod. By turning this hand-wheel the gun may be swivelled round.

A Motor Wagon that is capable of tipping its load is the subject of Model 453. These wagons may be seen any day in every town or city in use for various forms of transport where the load is to be quickly discharged. Coal merchants, road contractors and building firms generally possess a number of these useful wagons.

The model is easy to construct, and even the tipping arrangement is clearly shown in the illustration. Tipping is effected by a handle secured on a 57-toothed wheel, which engages a ½" pinion mounted on a rod. A worm is also secured on this rod and engages another ½" pinion, which is secured to an upright screwed rod, revolving freely in a coupling, being retained in position by a collar. The wagon is tipped or restored to its original position by respectively turning the handle in one (Continued on page 84)

# ELECTRICITY Of series of Splendid Articles Specially written for Meecano Boys

### I. SOME INTERESTING EXPERIMENTS WITH STATIC ELECTRICITY

ELECTRICITY has a fascination for almost every Meccano boy. There are few boys who do not, at one time or another, wish to take up electrical

engineering as a profession. An electrical engineer finds it easy to conjure light, heat and power out of the most ordinary materials. Truly he may be described as a modern wizard, whose achievements far exceed even the most fantastic dreams of the wizards of olden days.

Electricity was known over 2,000 years ago, but the form in which it was known ("static" electricity) did not enable it to be employed for any useful purposes. As we shall shortly learn, there are two kinds of electricity—"static" and "current," the former being at rest and the latter in motion, as the different names imply.

We may easily experiment with static electricity by briskly rubbing a pipe-mouthpiece, fountain pen, or stick of sealing wax on our coat sleeve. It then becomes charged with static electricity and in this condition we find that it will attract small pieces of paper, tobacco-ash and similar light objects, just as a magnet attracts pins and certain metal objects. (Fig. 1).

This power of attraction was known to the ancient Greeks, who demonstrated it by rubbing amber with fur. It is believed that this discovery was first made some 600 years B.C. by Thales of Miletus, an eminent Greek philosopher.

### An Ancient Greek Legend

Although they did not know it, the Greeks had taken the first step towards the foundation of the science of electricity in thus demonstrating the attractive power of amber. They regarded the phenomenon as a curiosity, believing that attractive power had been given to amber by the gods. Their legend tells how Phæton, the son of the sun-god, supposing—as do many boys to-day!—that he could do things better than his elders, decided to drive his father's chariot across the sky. He lost control, however, and came too near the Earth, with the result that the oceans were dried up and the land scorched. Jupiter, the lord of the heavens, seeing what was taking place, hurled a thunderbolt at Phæton and brought him to Earth. As a further punish ment his sorrowing sisters, the Heliades, were at the same time changed into

poplar trees, and their tears to amber.

This story is of more than passing interest, for the sun-god's name was Alector, "the shining one." Because

This article deals with the discovery and development of electricity and illustrates its principles, as far as possible, by means of interesting experiments within the reach of every Meccano boy. These experiments will give many hours of fascinating fun and are quite free from danger.

of this, amber became known as elektron, or "the shining thing," from which is derived the word "electricity."

To-day the Greek legend is set aside and the secret of the attractive power of amber is explained in a more scientific manner. For our present purpose we may say that the curious power is due to a charge of static electricity imparted to the amber as a result of rubbing. We shall consider this matter again, however, and will then explain in great detail exactly what takes place when the amber is rubbed.

A Famous Elizabethan: Dr. Gilbert

Having once found that they were able to summon this wonderful attractive force at will, the Greeks made no further study of it. In fact, as far as we know,

the subject seems to have been almost entirely forgotten until the 17th century, when Dr. Gilbert, of Colchester, a medical attendant of Queen Elizabeth, experimented with magnets.

### Dr. Gilbert, of Colchester

The magnet has been known from olden days, and

was regarded as an object of curiosity by the people of many nations. An iron ore possessing the peculiar property of attracting iron, and called the "lodestone," is mentioned in ancient Chinese records. The lodestone is also referred to by ancient Greek and Roman writers.

Dr. Gilbert was interested in the lodestone and studied its curious properties. He discovered among other things that when suspended by a thread a magnet always points north and south. To-day this principle is used as a basis of the magnetic compass, which enables our

ships to sail across the ocean and to steer a course to any point that may be determined. Although we know that magnetism and electricity are closely connected, it did not occur to Gilbert to suggest that the excited amber of the ancient Greeks could in any way be connected to his lodestone and magnets.

### Experiments with Static Electricity

Nothing further was done in this wonderful field of research until 1737. In that year Dufay, a celebrated French scientist, discovered that when excited by rubbing, substances other than amber have the same power of attraction for other bodies. We have already proved this by our experiment with the pipe stem. We may now perform some further interesting experiments with this form of electricity, by rubbing a glass rod (a piece of glass tubing or even a glass bottle will serve the purpose equally well) with flannel.

First of all make sure that the flannel and the glass rod are perfectly dry by warming them. Then hold the glass rod in one hand and rub it briskly with the flannel, held in the other hand. Hold the charged rod near some tiny pieces of paper, or some other light substance, such as tobacco ash or feathers. These objects will immediately be attracted, and will fly up to the glass rod and remain

### Electricity (continued)

adhering to it for a short space of time. This is, of course, a repetition of the experiment with the pipe-mouthpiece.

#### Attraction and Repulsion

Our glass rod enables us to carry out further experiments, however, for which the only additional "apparatus" required are some pith balls, which are simply pieces of pith from a branch of an elderberry tree. Slit a branch open with your pen-knife and you will find inside a white leathery lining. Cut out




Fig. 3. "Unlikes Attract"

a small piece about the size of a pea, dry it, and hang it on the end of a suspended silk thread, so that it hangs clear of the table. If pith is not obtainable a small feather or similar light object will serve the purpose almost equally as well. A suitable holder may be made by piercing

a piece of wire through the cork of a bottle, as shown in Fig. 2.

Charge the glass rod, by briskly rubbing it as before, and bring it near the suspended pith ball. It will then be found




Fig. 1. Pipe attracts light objects\*

to attract the pith ball towards it (Fig. 3). Notice that the glass rod acts as a magnet and that as soon as it touches the pith ball, the latter falls away and is repelled by the rod (Fig. 4).

### "Like Repels Like"

Now suspend a second pith ball alongside the first, by a second silk thread, fastened to the same support. Charge the rod as before and bring it near the pith balls. They are both attracted by the rod, but when the rod is taken away the balls immediately fly apart.

In our first experiment, when the electrified glass rod was brought near the pith, the latter was attracted by the

H. Guerrier

internal

(Ealing, N.)—


combustion

engine on so

small a scale

as you suggest

quite im-



charged rod because it (the pith) was uncharged. Whenthe pith came into contact with the rod, how-

ever, it b e c a m e A. Nairn Perth. W. Australia).— The subject of circular ele-

ments is conbeing stantly dealt with in

practicable. these columns. F. Spencer (Thurcroft).—We have designed a ball race element for use as a swivelling base for cranes, etc. This is illustrated in Model 401 in

the No. 3 Complete Manual. T. Tasker (Barnsley). - We list a special shoe for picking up the current from a centre rail. Thanks for suggested switch contact piece. We shall keep this before us when we make revision of the Electrical

Manual. R. P. Jones (Dulwich, S.E.).—A longer threaded pin commends itself and we shall keep the idea in mind. We do not see much advantage in single flanged plates and single angle strips. Smaller springs have already been suggested.

C. H. Wise (Grantham). - We have several good electrical models for inclusion in the Electrical Manual. when it comes under revision. 3½ x 2½ flat plates have many advantages, and we shall consider them. We hope to publish shortly an illustration of a Meccano electric loco designed to pick up the current from a third rail.

L. Herdman (Birmingham). - We do not think that a rack rod would be of general use, and its inclusion would not be justified for the one purpose you mention. Arthur Price (Warrington).-We do not recommend

the use of Meccano strips and girders in the formation of train track. Curves offer a very serious difficulty. Norman Ward (Kings Langley).—Our present milk van would serve equally well as a fruit van. They are almost identical in design.

C. G. Read (Guildford).—For what do you consider a perforated rod would be useful? A wider pitch worm wheel has already been suggested. We are exploring the possibilities of helical gears and propose increasing the variety of bevel gears shortly.

Fred Poultney (St. Helens).—An H-girder may be constructed from existing parts by bolting four angle girders to a flat girder.


J. Brackett (Upper Tooting, S.W.).-Rails with wooden sleepers are scale model equipment which we do not list. Thanks for criticisms of our rails, we are making considerable improvements in the method of manufacture.

\*This figure is reproduced from "The Romance and Reality of Radio," by permission of Messrs. T. C. & E. C. Jack Ltd.

electrified; here again, as "like repels like," it was at once driven away. For the same reason, the two pith balls repel each other, because they have both received from the glass rod a charge of a similar kind.

### Positive and Negative Charges

kinds of static electricity, which he called "vitreous" and "resinous." These to-day are known as "positive" and "negative," represented by the signs + and —. In static electricity a positive or a negative charge depends on the substance used for the experiment, and



In the next instalment of this series we shall demonstrate this more clearly by further experiments with the charged glass rod. We shall also describe how you may obtain sparks from your cat, and other equally interesting phenomena.

### MONTHFurther Experiments in Static Electricity

Ronald Stansfield (Southampton).—Corner brackets No. 133 and architraves serve the purpose of bracing

pieces. R. J. Mellan Amersfoort, Holland).-We have recently introduced a flanged disc of about 5" diameter which we think would serve the purpose of your suggestion.

W. F. Coates (London, S.W.).—(1) The small flanged disc attached to the face plate forms a flanged wheel of 21" dia. (2) We have the matter of single angle

strips already before us. W. G. Roberts (Hove, Sussex).—(1) Wrap the cord two or three times around the crank handle and tie with two ordinary half hitches. This will make a secure fastening. (2) We are afraid we cannot follow your ideas for eye-pieces of the same sizes as the perforated strips. (3) A station for use with Hornby

be available this year. C. W. Cubitt (Ipswich). - We are at the moment

trains is already on the market. Tunnels, Water

Tanks, Level Crossings and Signal Boxes will probably

engaged on a suitable sliding action. Edgar Plunkett (Dublin).-We shall consider the addition of a flange to the clockwork motor.

R. Stimson (Lowestoft).—Boat equipment such as you suggest would have no general use. Ewart Clee (London, N.W.). - We are bringing out a

variety of signals this year. E. Robertshaw (Nelson). - We are already giving the matter of a double crank shaft close attention.

L. R. Stockdale (Thirsk, Yorks.).—The increased perforation of the sector plate is under consideration. Will Kidston (London, N.).-We are preparing a further variety of train accessories this year, and shall

announce full particulars in the "M.M." in due course. J. Denis (Keighley, Melbourne).—(1) We have not yet found any uses for cams in Meccano construction. (2) Compression springs may easily be made from the expansion springs by simply extending the coils.

A. H. Miskin (E. Warwick, Queensland). - Your list of suggestions is interesting, but most of them duplicate existing parts. Under your heading marked 4 instead of using a bolt as a bearing for a wheel, we recommend the employment of a threaded pin.

D. J. Davies (Tottenham, N.).-Nearly all the train accessories you mention are already in course of preparation. Announcements concerning them will be made shortly.

J. Aighton (Clayton-le-Moors). -- Such a part as you suggest could not be made from one piece of metal. Since you admit that this formation may be obtained from existing parts, there would be no object in introducing a set piece to carry out the same functions.

B. Condon (Chiddingstone). - The difficulty about curved sections is determining the most useful diameters.



and new ways of making Meccano model-building attractive. We are always pleased to hear from any

Meccano boy who has an idea which he considers will be useful in the Meccano system. James Stevens (Kingston). - We have in mind further

new types of rolling stock for Hornby trains. It is our intention to make the series as comprehensive as possible. H. Oddie (Carranballac, Victoria).—(1) Regret, but

we are not able to follow your suggestion for a cup with a boss and cone plate. (2) Circular sections are having our attention.

Neil Shimmin (Leeds). - Meccano strips and girders do not make satisfactory rails for a train system. We already list a signal for Hornby trains.

G. D. D. (Windermere).—We are exploring various suggestions for a sliding gear. Squared rods offer some obstacle in the matter of bearings.

R. Manger (Guernsey).—We are afraid a hook such as you suggest would not overcome the twisting trouble. Moreover, it would be very costly to manufacture.

Leonard Lumb (Golcar).—We do not stock rubber "tyres" on account of their perishable nature.

Trevor Eden (Nelson).—We are interested in your photograph showing the addition of lamps to your model chassis. No doubt the fitting of this lighting installation has afforded you a considerable amount of entertainment.


Leslie King (Hyde).-We think that the present range of wheels offers a fairly good selection. In support of your suggestion we have already introduced a flanged disc and pulley wheel of approximately 51" diam., and also rim segments to form a wheel with a diameter of 114".

W. Womersley (Sheffield). - Your suggested rod with flatted ends and pierced is alright to a certain extent, but in no two instances would the same size be required.

# HORNBY TRAINS

### THE TRAINS WITH THE GUARANTEE


A most valuable and remarkable feature of the Hornby Train is that it can be taken to pieces and rebuilt just like a Meccano model. All the parts are standardised, and there is as much fun taking Loco, Tender, Wagon, and Coaches to pieces and rebuilding them as there is in playing with them. Any lost or damaged parts may be replaced with new ones.




### HORNBY TRAIN PRICES

-6-			110	• 1	
Goods Set		4.5.6	25/6	Wagons each 3/9	
Passenger Set	***		35/-	Tenders 3/6	
Locos	# W /E	each	16/-	Passenger Coaches ,, 6/6	

Goods Set		45/-	Wagons		each	3/9
No. 2 Pullman Set	24.4	70/-	Tenders			4/-
Locos	. each	30/-	Pullman Cars	***		16/-






No. 1 PASSENGER TRAIN


No. 1 GOODS TRAIN

# ZULU CLOCK TRAINS

The Zulu Clockwork Train is a cheaper type of mechanical train, the chief characteristics of which are fine and durable mechanism and immense strength of construction in all parts. The Zulu Loco is well designed and efficient, and will give long and excellent service. Richly enamelled and highly finished; fitted with brake and governor; non-reversing.



ZULU GOODS TRAIN



ZULU PASSENGER TRAIN

### Zulu Train Prices

Goods S	iet	0.0.0		18/6
Passeng	er Set			25/
Locos	***		each	10/6

### GUARANTEE

Hornby and Zulu Trains are tested, and their efficiency is guaranteed. A form of guarantee is furnished with each loco, and we undertake to repair, or replace, at our option any loco that fails to run satisfactorily from any cause other than misuse, within 60 days of purchase.

### Zulu Train Prices

Tenders	***	***	each	2/6
Wagons		* * *	9.2	3/-
Passenger	Coa	ches	,,,	5/-



### TANK LOCOS

### Hornby Tank Loco


The Hornby Tank Loco is a powerful model embodying all the characteristics of the Hornby Train. It is 11½" in length and is fitted at both ends with a special bogey.

Price .... 32/6

### Zulu Tank Loco

A strong and durable loco capable of any amount of hard work; richly enamelled and highly finished; fitted with reversing gear, brake and governor.


Gauge 0, in black only ... 12/6



FROM ALL MECCANO DEALERS

# Stronger Than A Thousand Men

A GIANT BUCKET CHAIN EXCAVATOR



Monster appliances, such as this Bucket Excavator, have made possible many great engineering achievements

THE attention of all Meccano boys has recently been drawn to the Ruhr Valley by the activities of the French, who have occupied this district in the hope of exacting reparations from Germany that were not previously forthcoming. One of the principal towns of the Ruhr is Essen, now occupied by the French troops. Essen is a large manufacturing town situated in the heart of the German coal mining district of the Ruhr. The town itself is particularly noted for the fact that Messrs. Krupps' works are situated there.

At these great engineering works all manner of appliances are manufactured. During the war the works were the centre of feverish industry, day and night, supplying the German army with munitions and war materials of every description. It was here that the "Big Berthas"—the long range guns that shelled Paris—were made, as also were most of the giant howitzers that are now familiar objects in parks and public places in this country.

Now that arms and other war-like materials are no longer in demand, Krupps'

works are engaged in the manufacture of agricultural implements and similar machines of a more peaceful nature.

We are able to illustrate one of these machines—a giant dredger. These dredgers are used for levelling surfaces in canal work, and for clearing farm-land by removing surface rock and other materials in order to lay bare the soil beneath. They are also used to obtain lignite or brown coal, which generally lies near the surface, and in connection with the mining of all kinds of minerals.

This remarkable dredger runs on rails. The frame arm that carries the bucket chain may be lowered or elevated to any required position in which to work. If lowered to the ground, or beneath the level of the ground, it may be used for subterranean excavation.


It was appliances of this type that made possible such wonderful achievements as the cutting of the Panama Canal and other similar great engineering works, that have so greatly benefited mankind.

It is of interest to note that in principle these machines are very similar to their "sailor brothers"—the sea-going bucket-dredgers. In both cases the buckets which scoop up the material are on an endless belt. When in a river the bucket-dredger lowers the arm carrying the buckets down to the river bed and scoops up the material. The mud or sand is then loaded into a lighter or "hopper" alongside, which is towed out to sea and discharged.

The story of dredgers and dredging is a very fascinating one indeed, including as it does the remarkable ships that discharge their loads by dropping the vessel's bottom out while at sea, and dredgers that can fill themselves with 10,000 tons of material in less than an hour. An interesting article giving illustrations and full particulars of these wonderful machines, which are convincing examples of the marine engineer's skill, will be published in a future number of the "M.M."

# GIANTS OF THE RAILROAD

American and British Locomotives Compared



No. 7857. A Giant Locomotive of the Union Pacific Railway Company

THOSE of our readers who are interested in railways—and judging by the continual flow of queries on railway subjects, there must be many tens of thousands of such—are all familiar with the fact that the giants of the locomotive world are to be found in America. In that country the cry for more speed and power has been developed to such an extent that some American locomotives are built on proportions so gigantic as to make us pause with wonder and awe.

Look, for instance, at the huge monster illustrated above! Note its gigantic proportions as compared with the two

men standing alongside. Note its eight coupled-driving wheels, its enormous boiler, the height of the cab, and lastly its great length. Then by way of contrast compare the photograph with that of Stephenson's early locomotive on page 61 of this issue and you will realise what is meant by the "triumph of engineering"—more especially so

when we remember that there is an interval of barely a hundred years between the date of these two locos.

### Why America Builds Giant Locos

Although American locomotives may lead in point of size, the locos of British railways make quite a good show, and in this article we shall compare one type with the other. In doing this we may remember that American locomotives are built for a different gauge and are designed for a more varied class of work than those used in our own country.

America will probably always lead the way in this respect, for it is not necessary

for us to have such powerful locomotives. The "Caerphilly Castle" is the most powerful express passenger loco in the British Isles. It is the first of a new class of ten, each of which will be named after some famous castle, with numbers running from 4073 to 4082.

Belonging to the 4-6-0 class, these new locos incorporate several important departures from previous designs. In the first place larger cylinders have been fitted, and steam is supplied from a new type of boiler. This type of boiler, which is now becoming increasingly popular in locomotive construction, has the usual

The amazing engineering progress of the past hundred years is nowhere better shown than in the evolution of the locomotive. In this article the writer shows how the locomotives of America exceed the size of those in Britain, although the home of the locomotive was in England. He shows also that the reason for this is governed largely by local conditions. A comparison of American and European locomotives is always interesting—more particularly so at the present time, after the recent introduction of the new and powerful "Castle" type of the G.W. Railway.

standard features, but the dimensions have been considerably increased.

### New Type of Cab

The tractive power of the ordinary four-cylinder engine now in general use is 27,800 lbs., but this new type of engine increases the effort to 31,625 lbs. This increase has been effected by giving an additional inch to the cylinders, making them 16 in. in diameter, the piston stroke of 26 in. remaining as before.

The valves are of the inside admission type and are connected by horizontal rocking-arms and driven by two sets of Walschaerts' motion between the frames.

Steam is conveyed to the outside cylinders by external pipes brought through the smoke-box sides and directly connected to the steam-chests, the inside cylinders being supplied through passages in the saddle.

The coupled wheels retain the standard diameter of 6 ft. 8½ in. and the bogie wheels the diameter of 3 ft. 2 in., and no change has been made in the total length of the wheel base, except to increase by 1 ft. the overhang of the rear end. This has made it possible to fit a new type of cab, the roof of which has been extended and the sides fitted with larger windows. With the exception of the regulator handle,

no fittings project into the cab, thus giving more room for both driver and fireman, for whom tip-up seats have also been provided.

### An American Giant

Having gained some idea of the improvements in this new British loco, let us now compare them with one of the giants of America.

No. 7857 is one of several locos that were recently built to the order of the Union Pacific Railway. These have proved highly satisfactory for hauling heavy goods trains over the very hilly country traversed by this railroad. They embody all the latest engineering improvements, and may be said to be representative of the latest phase of American locomotive construction.

Perhaps their most interesting features are to be found in the boiler and superheater, together with their various accessory apparatus. The boiler is of the usual straight-top type with an inside diameter of 82½ in. and a pressure of 200 lbs.

The grate is of the table type, is equipped with a power-operated shaker, and has an area of 84 sq. ft. It is fed by an Elvin mechanical stoker, driven—as are

auxiliaries—by This superheated steam. mechanical stoker does away with the necessity for manual labour on the part of the fireman and is both compact and light-important considerations in the construction of locomotives of this type.

The inner firebox, which is made of steel, is 10 ft. 6 in. in length and 8 ft. in width. A double firebrick arch is used instead of the usual combustion chamber. It consists of two sets of refractory

bricks, supported on rows of four arch tubes, which greatly increase the heating surface and materialy promote water circulation.

#### Large Tubes Fitted

The tubes contained boiler barrel are relatively size on large account of the fact that a number of them are coupled by the elements of

the superheater. This superheater is of a greatly-improved design and imparts a higher temperature to the steam than that given by the ordinary pattern. It allows a greater steam area through

the element tubes, besides permitting the passage of larger volume of gas, which in turn ensures a better transference of heat. Heat losses at the stack, too, are greatly reduced by this There new arrangement. are no dampers, as in British locos, and as the regulator is between the superheater and the cylinders, protection heating against excessive when the engine is shut off is afforded by the flow of

steam to the blower, pumps and other auxiliary apparatus.

The total superheating surface is 1,331 sq. ft. and including arch tubes, flues, firebox, heating surface and tubes, the total heating surface, inclusive of superheater, is 6,302 sq. ft. Consuming bitu-

minous coal at the rate of 138 lbs. per hour per square foot of grate area (or a total of 9,180 lbs. per hour) the boiler shows an hourly evaporation of 56,900 lbs. of

There is a great interest amongst our readers in railway matters. We shall endeavour to include more articles on this subject in our future issues, if space permits. The Editor will be pleased to consider any articles, photographs, or sketches dealing with railways, locomotives and kindred subjects. Payment for those published will be made at our usual rate.

water, which according to the Cole method of calculation (a system in general use

> among railway constructors and engineers) corresponds to over 2,735 boiler horsepower.

easily against the injector at a full capacity of 5,000 gallons per hour.

The cab is of the Canadian Pacific Railway type and the fittings, in addition

> to power reversing gear, include a pyrometer and two reflex water gauges of the Ashcroft type. The right side gauge is tapped into a water column which is in turn tapped into the back head of the boiler, while the

left gauge is tapped directly into the boiler head.

#### The Latest in Tenders


A novel departure has been made in the shape of the tender, which somewhat

resembles a petrol tank Nearly wagon. circular in shape, it is built on the usual frame and runs upon two six-wheel bogies. It is fitted with an up-to-date and improved water scoop and has a capacity of 12,000 gallons and 20 tons of coal. In working order tender this 242,100 weighs lbs., which added to the weight of

the engine, i.e., 348,000 lbs., gives a total for both of 690,100 lbs.

In spite of its huge weight and apparently complicated arrangements, however, the engine is exceedingly easy to handle in

practice, special attention having been given to this point in both the design and construction. Manual labour is practically eliminated and all controls are grouped conveniently on either the driver's or the fireman's side. The whistle, cylinder-cocks and bell (the latter device being a feature never seen on our English locomotives) are all actuated pneumatically.



Union Pacific 7857

[G.W. Railway Co.

Photo by]

The New Four-cylinder "Caerphilly Castle" of the G.W. Railway

### Power-operated Accessories

Specification

Length of engine and tender

stroke

Heating surface (firebox)

Water capacity of tender

Maximum tractive effort

(tubes)

Gauge of track

Boiler diameter

No. of fire tubes

Grate area

Cylinders, diameter

,, flues

Total heating surface

The firebox door, reversing gear and sanders are all operated by compressed air. The usual electric head, cab and rear lights are provided, and steam-

Caerphilly Castle

4 ft. 81 in.

65 ft. 14 in.

201 2 in.

14 5\ in.

30.28 sq. ft.

163.76 sq. ft.

2,312 sq. ft.

3,500 gallons

31,625 lbs.

1,885.62 sq. ft.

16 in.

26 in.

operated grate shakers for clearing or dumping the fire are additional improvements. When not delayed by any obstructions, these engines cover the entire railway division in 5 to 6 hours drawing a full load. They steam well,

and keep the pointer on the 180 mark

Comparative Details

From our description it will be seen that the Union Pacific locos are very different in construction to the G.W.R.'S "Castle" class, or, indeed, to any of our British locos. The classified comparison of heating surfaces, grate areas, boiler diameters, etc., given will make the contrast even more clear.

### Interesting Paragraphs

The late Sir James Dewar, the discoverer of liquid air and inventor of the Thermos Flask, was known as a scientist throughout the world. He had received honours and distinction at the hands of nearly every scientific body in existence.

The Old Colwall Tunnel, which takes the Great Western Railway through the Malvern Hills and has done service for more than fifty years, is to be replaced by a new tunnel. This will run parallel with the old tunnel at a distance of 45 ft. from it. It will be 1,600 yards in length, will cost about £200,000, and will take about two years to construct.

Another most important discovery has been made in one of the Sheffield laboratories. This is a tarnish-resisting alloy, which is in reality "stainless silver." The new product is called "Silanca," and owing to the small percentage of other metals that it contains, it is entitled to carry the silver hall-mark.



# The New "Meccano" Jersey

By Arrangement with "Meccano" Ltd.

24" 5

0 28

30" Chest 9/9

Navy/Saxe Light Fawn/Brown

Mid Grey/White French Grey/Mole

Obtainable ONLY from Jaeger Depots and Agencies

There's a Jaeger Shop in every Town. Address on Application.



### JAEGER

Head Retail Depot: 352/54, OXFORD STREET, LONDON, W. 1. Wholesale and Shipping: 95, MILTON STREET, LONDON, E.C. 2.

NO BOY OR GIRL can afford to be without the world-renowned and largely-advertised

# SECCOTINE

(Ragd. Trade Mark)

Tubes 4½d., 6d., 9d. Everywhere.

The best general adhesive the world knows. For wood, leather, bone, paper, etc., objects large or small. Used in bulk for manufacturing purposes. Of great utility to boys and girls who long to make things.

# FIRMAS (Heat Seccotine)

(Regd. Trade Mark)

Tubes 6d.

For glass, china, delph, etc. Articles joined with it can be boiled without coming asunder.

McCAW, STEVENSON & ORR, LIMITED,
The LINENHALL WORKS, BELFAST.

Telegrams: "GLACIER, BELFAST."

Telephones: 4261 (3 lines).

# Motoring in Shakespeare's Country

By Master Brian Bentley

(This Essay won the First Prize in our recent Holiday Essay Competition).

OTORING is a delightful method of spending a holiday, and I do not think that I enjoyed any tour



Shakespeare's Birthplace

as much as the one we had last summer, when we went through the country where Shakespeare lived. We started out from Bridgend for Uppingham about half-past five on a Sunday morning in July. We had two objects in view—one to have a short holiday, and the other to see Uppingham

School, where I was to go next term. Morning and evening seem to me to be by far the best times for motoring in the summer, for the air is so beautifully fresh and cool. As you rush through it it makes you feel that you would like to go on and on for ever! That particular Sunday morning was perfect. Not a soul was to be seen, except some farmlabourers going to attend to the cattle, and a lonely wayfarer trudging along the deserted lanes.

We first passed through Caerlon, that romantic old place which was the scene of many of the exploits of

King Arthur and the Knights of the Round Table. Having passed Monmouth and the River Usk, we reached the Valley of the Wye, where the scenery became more and more beautiful. It was here that we came across a relic of the past—a tollgate. Outside the little lodge was a notice stating the various charges, and beginning with the quaint "toll for an ass laden." Further down came the "toll for a motor vehicle," so that the ancient beast of burden was placed side by side with the modern vehicle of transport.

The next place we came to was Ross, where there is an old red Market Hall. It was here that I took out my camera to put in a new film and take a photograph. But alas! I found I had no empty spool on which to wind the film, and I was forced to pass the old Market Hall without taking a photo of it. However, I was able to take it on my way home, but it was heart-rending to have to leave all the beautiful views until the return journey because I had no film!

A rather amusing incident happened while we were in Ross. Looking round for somewhere to get a spool, I noticed a shop open. We enquired for a V.P.K. spool


and the man said he thought he had one. After a search under the counter he returned with a spoon / I am sure I do not know

what he thought a "V.P.K. spoon " was!

Our next place of call was Gloucester, where there is a beautiful cathedral. We did not stop, however, because of the small-pox epidemic, and also because we desired to get to Tewkesbury as quickly as possible for some breakfast! Tewkesbury is the "Nortonbury" of that famous book "John Halitax, Gentleman." There again, ancient and modern lay side by side, for in the old coffee room of the

Bell Inn was a notice that "Marconiphones are sold here! "

The Abbey Church is in a wonderful state of preservation and looks very grand from outside, but the interior is even more lovely with its stained-glass windows. Its 800th anniversary was celebrated last year, and there are few buildings in all England that have so many historical associations. It es-



Memorial Theatre, Strattord-on-Avon

caped the destruction of abbeys and churches in the reign of Henry VIII, and stands to-day almost exactly as it was built in the early part of the twelfth century.

From Tewkesbury we travelled through the heart of the apple-growing country to Evesham, where there is a glorious view from the river-bank. Boats and punts

were moving up and down the river, and a church surrounded by trees added beauty to the scene. Between Evesham and Stratford-on-Avon we passed many fine old cottages with white fronts lined with black wooden beams, and surrounded by pretty little gardens. These quaint little houses became more and more numerous as we neared Shakespeare's native town.

Stratford itself is a picturesque old place. One thing I noticed particularly was the way in which the atmosphere of old England seemed still to be preserved. Even the modern houses are built after

the style of the old ones, in order not to spoil the old-fashioned appearance of the place. I was disappointed on the way home that I had no time to take a photograph of Anne Hathaway's cottage, which is some distance out of the town. However, I took a photograph of the house in which Shakespeare was born, and another of the Memorial Theatre, which, of course, is known all over the world. The view from the grounds of the latter was nearly as lovely as that at Evesham, being also of a river with a church on the bank.


From Stratford we went to Warwick, eight miles away, and here I got a photograph of one of the corners of the Castle. Seen from the street, the tower with the sunlight shining on it made a very pretty picture indeed. After passing through Warwick we did not come to many places of interest, but the country was still as beautiful as ever. Near Leamington the trees often met overhead, forming a natural archway of foliage, broken now and then by a patch of sunlight. At Leamington I felt like stopping to see the famous

> Meccano Club, but remembered in time that it was Sunday! Between Leamington and Market Harborough there seem to be multitudes of small villages, but a most confusing medley of villages came between Market Harborcugh and

Uppingham.

According to our guide book we had to go through Rockingham and Coltingham. Here and there we found sign-posts directing us to these places, but, although we followed the road along which they pointed we never found either of the places. At last, however, we


got to Uppingham by another route. We were tired, which is not surprising, for we had travelled about 190 miles that day. We went to see the school that night, and started for home at eleven o'clock next morning, where we arrived without a mishap after a most enjoyable trip through glorious country.



The Avon at Stratford

FOR DEPENDABILITY OF OPERATION USE

# "IGRANIC" RADIO DEVICES






### HONEYCOMB INDUCTANCES

(De Forest Patent No. 141344).


These world-famous coils are renowned for their high efficiency, low self-capacity, small absorption factor and minimum high frequency resistance. No deadend losses. Each turn surrounded by air pocket. Made in two types, gimbal and plug mounted. Wave lengths approximately 100 to 25,000 metres. The only coils that uphold their claim for negligible losses. Prices vary with sizes.



### INTERVALVE TRANSFORMERS

(Patent No. 205013).

Designed for the distortionless reproduction of speech and music. The steel shroud effectively shields from external interference. Recent improvements in design render it the finest amplifying transformer obtainable. Prices: Shrouded, 21/-. Open, 20/-.






### FILAMENT RHEOSTATS

(Patent No. 195903).


A splendid instrument for filament control under all conditions. Novel method of construction ensures smooth and silent operation. Designed for individual valve control. Adjustable contact finger permits of resistance values from zero to four ohms by fine variation. Supplied in two types, plain and vernier. Prices: Plain, 4/6. Vernier, 7/-.



### TYPE "H" VARIOMETER

Recommended for use in the aerial circuit of crystal and valve sets. Wave length range approximately 150-600 metres, with P.M.G. standard aerial. Stator and rotor best quality mouldings, windings self-supporting and impregnated solid. Price, with knob, dial and fixing bracket, 15/-.

knob, dial and fixing brackets, 19/-.



variable over wide range. Price, with

Write for Leaflets Z. 162.

Glasgow.

Manchester. Queen Victoria St., Bradford.

LONDON.



Works: Elstow Road, BEDFORD.

Cardiff. Newcastle. Birmingham

# Enter our Essay Competition

First Prize: MODEL-DE-LUXE SCOOTER.



Model-de-Luxe Scooter

Boys! Get the most out of lifebuy an AUTO-SCOOTER.

THE popularity of the AUTO-SCOOTER amongst boys and girls is becoming greater than ever. Think of the exhilarating joy of gliding along on a fine spring day with the wind cutting your face and your whole being thrilling with keen excitement! Isn't it a happy thought? Our AUTO-SCOOTERS are built on scientific lines and will give long and excellent service, even with the roughest handling.

Be sure you ask for an AUTO-SCOOTER for your next present!

The Auto-Scooter is the Sporty Toy for the Sporty Boy. Prices to suit all pockets. Send for list of 6 different models.

### Splendid Essay Competition for boys under 14

WHAT YOU HAVE TO DO.

Write an Essay of not more than 500 words on "Why I should like an AUTO-SCOOTER for my next present." Then send it to the Editor of the "Meccano Magazine." Closing date for entries from the United Kingdom 31st March, Overseas 30th April next. The Editor of the "M.M." has kindly consented to act as judge, and for the two best essays we will give the following—

> First Prize: Our Model-de-Luxe Scooter, as illustrated. Second Prize: Our Popular Model with Solid Tyres.


The New Auto-Scooter Company, CHESTERGATE, STOCKPORT. STOCKED BY ALL LEADING TOYSHOPS.



Some splendid new ones are being prepared and will be announced in our future issues. On page 79, particulars are given of the £250 Championship Contest for the best models, which every reader of the "M.M." should enter.

# For Lynx-Eyed Readers

FINAL SET OF PUZZLE PICTURES



### WHAT YOU HAVE TO DO

Above is the third and last set of Puzzle Pictures in this novel competition. Each picture represents part of some model in the current 0-3 Meccano Manual of Instructions.

Readers of the "M.M." who know their Manuals well, should have no great difficulty in finding out from which models the Puzzle Pictures have been taken. As each one is identified, write the number of the model beneath the Puzzle Picture, until all six pictures are solved. Then turn to the other two sets, which appeared in the January and February issues, and write on a postcard the numbers of the pictures, and against these write what you think are the numbers of the models from which they are taken. When all eighteen numbers have been set down, write your name, address and age on the postcard and send it to "Puzzle Pictures," Meccano Magazine, Binns Road, Liverpool. No other matter should be written on the postcard, except the

solution to the puzzles and the competitor's name, age, and address. Entries should reach this office by March 31st (Overseas, June 30th).

Competitors should remember to write neatly, as in the event of a tie, neatness will be taken into consideration. If no competitor succeeds in numbering all the models correctly, the prize will be awarded to the competitor who sends in the best effort. Other prizes will be awarded in order of merit.

FIRST PRIZE:—Hornby No. 2 Passenger Set.

SECOND PRIZE:—Zulu Goods Set. THIRD PRIZE :—Electric Motor.

CONSOLATION PRIZES:—12 Meccano Writing Pads and 12 Complete Manuals.

Remember that this contest closes on March 31st, and on June 30th for Overseas readers. Make sure of being in time and send in your attempt to-day. The results will be published in the May number of the "M.M."

### Competition Closing Dates

1924 25 Mar. Puzzles (see p. 83).

Puzzle Pictures. 31 Mar.

Stamp Essay.

15 April £250 Championship.

### Overseas Closing Dates

1924 31 Mar. Essay.

30 April Drawing.

30 May £250 Championship.

30 June Puzzle Pictures.

Stamp Essay.

### Seventh Photographic Competition

Our photographic competitions continue to attract large numbers of entries, and we have pleasure in announcing another competition. This is the Seventh Photographic Competition, and, as before, there will be no restrictions except that the photographs entered must have been taken (i.e., exposed) by the entrant. The plates or films may have been developed or the prints made by others. This fact must be stated on each entry, however, as naturally if two photographs tie for first place, preference will be given to the one that is the sole work of the competitor.

The subject of the present competition is:-AN OUTDOOR SCENE

and the contest will be divided into two sections: (A) For those of 16 years of age and under, and (B) for those over 16 years of age.

The Prize will be goods to the value of 10/6, to be chosen from our catalogue by the winner. Closing date 30th April next. (For Overseas Readers 30th July).

### FOR OVERSEAS READERS Drawing Competition

As already announced, a drawing competition has been arranged in response to numerous requests, the subject to be: "The Editor of the 'M.M.' as I imagine him to be." In this competition the drawings may be of any size and the subject may be treated in any manner desired, i.e., it may be either in black and white, pencil, crayon or wash.

There are no restrictions, except that the drawing must, of course, be the unaided work of the competitor. The competition will be divided into two sections:-

(A) Boys under 12 years of age. (B) Boys of 12 years of age and over.

A prize of a Hawk-Eye camera, manufactured by the Kodak Company, will be awarded in each section. The closing date for entries Overseas is 30th April, 1924.

### Essay Competition for Stamp Collectors

Our last essay contest (the result of which will be announced next month) clearly showed that there are many thousands of keen stamp collectors among readers of the "M.M." It has been decided to hold another essay competition, this time the subject is "My Favourite Stamps and Why I Like Them." Some special set, or stamps of a certain colony or even stamps of a country should be chosen and described, and the reasons for your choice given. The essay must not exceed 500 words and is to be written neatly on one side of the paper only. Envelopes containing the entries should be marked "Stamp Contest" in the top left hand corner and sent to the Editor of the "M.M." Binns Road, Liverpool.

The first prize will be stamps to the value of 10/6, to be chosen by the winner himself from any firm advertising in the pages of the "M.M." Make your choice when you send in your essay, and give full particulars of the stamps required, so that the prize may be sent direct to you in the event of your success. Closing date March 31st (Overseas Readers: June

30th, 1924).

# "Why We Should Buy British Toys"

### Results of Interesting Essay Competition

There is little doubt of the correctness of the New Auto-Scooter Company's claim that their scooter is "the Sporty Toy for the Sporty Boy." Hundreds of sporty Meccano boys all over the British Isles made valiant efforts to secure one of the splendid prizes awarded by this enterprising company, and the essays on "Why We Should Buy British Toys" showed considerable care and thought. The winner of the Competition was Master G. S. Marsh, of Thorn ton-le-Fylde, Preston, and the first prize of a Model de-Luxe Scooter fitted with pneumatic tyres, has been despatched to him. The essay entered by Master R. Shearer (age 8), of Bradley, Keighley, was adjudged second, and he has been awarded the second prize of a Popular Model Auto-Scooter.

So great has been the interest taken in the Competition that the New Auto-Scooter Company have decided to conduct another contest, so that our many thousands of Overseas readers will have an opportunity of competing. Full particulars of this second competition are given on page 72, and although the closing date for the United Kingdom is not until March 31st. readers are advised to send in their entries as soon as possible.

Mark your envelopes "Auto-Scooter" in the top left hand corner and address to the Editor, the Meccano Magazine, Binns Road, Liverpool, who has been asked to act as judge.

# Doyou 85 ? Wireless?

results at the lowest cost. POPULAR WIRELESS, the most popular and practical of all wireless weeklies, will tell you how to construct or repair any type of receiving set and how to enjoy this popular hobby to the full.

Week by week it is packed with chatty broadcasting news and endless valuable hints and tips. It is authentic without being too technical, and contains articles and special features for both amateurs and experts. For the young wireless enthusiast there are two regular pages entitled "The Junior Amateur" and "Practical Ideas for the Amateur." Several pages are devoted to Radio Questions and Answers. Sir Oliver Lodge, F.R.S., D.Sc., acts as Scientific Adviser.

Buy a copy of this

Splendid Paper

TO-DAY

# DOPULAR S WIRELESS

Every Friday

Of All Newsagents


# Interior of Great French Radio Station

Our photograph shows one of the enginerooms at the powerful French radio station of St. Assise. How different a modern radio station looks as compared with the earlier stations which were often accommodated in make-shift premises and were equipped with large spark gaps and giant condensers of glass. To-day only the most modern appliances and machinery are used and the "layout" of the station is on recognised engineering lines.

At St. Assise huge aerials, suspended by 800 ft. masts, stretch like a huge net over the station buildings. The buildings are commodious, beautifully lighted and ventilated, whilst the engines, dynamos and alternators are well kept and carefully looked after—as befits the world's largest radio station.

Our illustration shows three Diesel engines, one of 1,800 h.p. and two of 80 h.p. This type of internal-combustion engine is becoming increasingly popular for radio work.

We hope to publish a fully illustrated description of this remarkable radio station in one of our future issues.



Photograph]

Interior of Engine Room, St. Assise, France

[by S.I.B.



Austin N. Pooley (Cambridge).—(1) The wire mentioned will be quite suitable. (2) A buzzer in series with the primary will be quite suitable for an interrupter. (3) The spark length depends on several factors, such as the amount of primary voltage, the magnetic quality of the iron core, the material used as spark points, efficiency of condenser and quantity of winding. You will see, therefore, that the spark length can only be ascertained by actual experiment. (4) The secondary coil must be wound over the primary coil in the same direction as the primary.

J. McCaskell (Gairlock).—(1) Brass spacing washers may be used for the condenser in your receiving set (2) It is not necessary that a 5½" × 3½" plate should be used for the mounting of the condenser; you may mount directly on the board by means of Meccano brackets.

F. Lambert (Rothwell).—Owing to the screening effect of the intervening Pennine Range it will not be possible for you to receive telephony broadcast from Manchester.

E. C. Varch (Hull).—(1) The price of the  $2\frac{1}{2}$ " ×  $2\frac{1}{2}$ " special fibre plates is 2d. each. (2) You may connect up the fixed portion of the condenser by placing spring washers between the insulated discs. These discs are threaded on a screwed rod, and after all the parts are assembled the whole is bolted together by the fitting of nuts-on each projecting end of the screwed rod. (3) Yes, the holes are already drilled in the mounting board when you purchase it.

R. Goodfellow (Birmingham).—(1) The call letters of nearly all transmitting stations are to be found in the booklet published by the Radio Press entitled "The Call Book." This is obtainable at any bookstall, price 6d. (2) The Morse Code is illustrated in the Electrical Manual, price 1/8 post free.

J. Wilson (Manchester).—I am pleased to know that you are enjoying the nightly programme broadcast from Trafford Park. Your instruction leaflet will give you the other information you require.

R. Griffiths (Doncaster).—The No. 2 Crystal Receiver is constructed of Meccano parts. These parts are particularly suitable for carrying out experiments.

C. Andrews (Maidenhead).—(1) As you are approxi-

C. Andrews (Maidenhead).—(1) As you are approximately 26 miles from London you should have no difficulty in receiving broadcast from 2 L.O. with a Meccano Crystal Receiver, provided your aerial is erected as high as possible and carefully insulated. (2) Although it is possible to use two crystals on a set it would not materially effect its power of reception, and I would advise you to use one crystal only. (3) Marconi House is the nearest broadcasting station to Maidenhead.



Mr. Louis J. Frank, superintendent of a hospital in New York, has installed a complete radio outfit with 150 headpieces for the use of patients. He believes that by this diversion, the minds of many of the patients will be taken off their ailments and that it will do much towards helping them to recover.

The Marconi Office in Liverpool—which makes possible direct wireless communication with France, Spain, Switzerland, Canada or the United States—is the first of its kind in the provinces. It is equipped with high speed transmitters and customers handing in messages for transmission abroad may wait in the office for their replies.

The London Broadcasting Station is to have a new transmitting plant in the near future. This plant will not be situated in Marconi House, Strand, as at present, but in all probability will be in Wardour Street, half a mile distant.

Lancelot White is one of the youngest wireless concert artists. He is seven years old and broadcast from 2LO the other day. "I couldn't see the audience," he said later, "but I knew thousands were listening to me, and it just bucked me up. I put my mind on the stories and forgot mother and the others in the room."

The Sheffield Relay Station, now in operation, was originally intended to receive by radio the programmes from Manchester and Cardiff and then relay them to the transmitter in Corporation Street by means of a land line. Now, however, the microphones of the Cardiff and Manchester stations are connected by land lines direct to the relay station at Sheffield.

An illustration of "freak" reception is given by the experience of a listener living in Merton Park, London. With a three-valve set, and at about three o'clock in the morning, announcements and music were clearly heard from Havana, Cuba. A wireless sermon and organ recital from an American station were also re-transmitted over an ordinary telephone line to the offices of a well-known London newspaper.

A very successful transatlantic test was recently carried out when wireless enthusiasts at Long Island, New York, distinctly heard piano playing, music and voices broadcast from Liverpool. The words, "Hello, America!" were also heard several times, spoken in a man's voice. The tests were continued the next night, when an address by Mr. Henry Ford was easily picked up by many amateurs in this country.

The first regular wireless telephone service in Europe is that between Copenhagen and the Isle of Bornholm. The striking feature of this new service is that although it is a combination of wireless with ordinary wired telephones, the telephone subscriber at Copenhagen does not require any special apparatus to be connected, via wireless, with a subscriber in the Isle of Bornholm.

Many amateurs are listening for American broadcast. American time is different to ours, and therefore the best time to listen is between 2 a.m. and 3 a.m. At this time it is dark both in the U.S.A. and in England, and there is also less interference from Morse. Under good conditions a two-valve set should succeed in receiving one or more of the large American stations.

# A Rattling New Serial

Commences in

# The BOYES OWN Report

FOR MARCH, 1924.

# A Son of the Dogger

Sam Reed's Adventures on the Wild North Sea.

By WALTER WOOD. Illustrated by GEORGE SOPER.

This Number also contains:

Two other Serials, Complete Stories, Special Articles, Hobbies, Field Club, Coins, Stamps, Ju-Jitsu, COMPETITIONS, and a splendid large plate in colour, entitled: Beating the "Charge" AT Dettingen (1743).

1/- monthly—and worth it!

Published at the B.O.P. Office, 4, Bouverie St., London, E.C.4.



A thrilling incident in the New Serial, "A SON OF THE DOGGER."

MAKE SURE OF YOUR COPY.
Of all Newsagents.

# Stamps for Sale (see also page 82)

(For Advertisement Rates see page 82).

SIXTY DIFFERENT STAMPS FREE to applicants for approvals. All ½d. each. Send postage.—Cox, 135, Cambridge Road, Seven Kings.

STAMP COLLECTORS! Be sure you get The Philatelic Magazine, the fortnightly stamp newspaper, 3d. from any newspaper, or 4d. post free from Publisher, 63, Windsor House, Westminster, S.W.1.

110 GOOD STAMPS including Togo, Tchad, Gabon, Senegal, Sudan, 6d.—Kraus, 137, Cheapside, London.



### GOLLECTIONS FOR SALE.

1000	diff.	inc.	Col	onial	s		7/3
3000	(E) (E)			,,		5	50/-
300	**	Wan	180				
		A	rmis	tice,	etc.		2/6
100	,,,	Fre	nch	Cols.			1/9
100	1 ,,	Pola	and				2/6
500		Unu	used	Stan	nps		9/9
				tamp		ub,	
	I	IOR	SMC	NDE	N.		

### 'ASIA' PACKET—FREE

25 selected issues including PERSIA (scarce Provisional), GWALIOR, Travancore, Ceylon, China (Ship), Deccan, Malay (Tiger), Patiala, Siam, Straits, etc. Ask for APPROVAL SHEETS and receive this fine packet FREE! Enclose 11d. postage.

FELIX SYKES, Stamp Importer, NEW BARNET.

### COLD COAST ALL MINT

KING GEORGE, Scripts, ½d. green, 1d.; 1d. brown, 1½d.; 1½d. scarlet, 2½d.; 2d. grey, 3d.; 2½d. yelloworange, 3½d.; 3d. blue, 4d.; 6d. purple, 7½d. POSTAGE DUES. 1d. black, 1½d.; 2d. black, 3d.; 3d. black, 4d. POSTAGE EXTRA.

ASK FOR MY NEW PRICE LIST.

ALEC KRISTICH (N.R.P. 279),
82, Marchmont Street, Russell Square, London, W.C.1.

FREE 25 Poland Stamps to those sending postage and asking to see Approval Sheets.

C. Florick, 179, Asylum Road, London, S.E.15.

50 French Colonies 9d. 50 Roumania 1/100 United States 1/- 50 Argentine 1/150 Germany ...1/- 300 Postage 1/150 Austria ... 1/- 50 Cards and
150 Hungary ... 1/- Envs. ... 1/Fine selection of Postage or Revenue ready.

I. Russell, Chetwynd, Shanklin Drive,

# STAMPS FREE

Westcliff-on-Sea.

9 rare unused POLAND, 25 to 2,000 marks (Cat. 4/-) to Collectors sending 1½d. postage, mention Gift 0.29.

Bright & Son, 164, Strand, W.C.2.

### "DIAMONDS" ARE VALUABLE.

Mr. J. R. D., Edinburgh, writes: "Please forward two more 'Diamond' Packets. THE LAST ONE WAS THE BEST PACKET I HAVE EVER BOUGHT."

### 1,000 UNSORTED STAMPS, 1/3 (from Convents abroad).

2 pkts., 2/5; 3 pkts., 3/6; 4 pkts., 4/6; 5 pkts., 5/6.
All Post Free (Abroad 3d. per packet).

O. Nerush, Importer (Dept. E.), 2-22, Cathcart Hill, London, N.19.

LOOK, BOYS! GRAND PACKET. Pictorials given away to applicants for approvals. Send postcard to-day. L. C. Jones, 13, North Road Bourne,

### 7 Bolivia Gratis

COMPLETE SET 1c. to 100c.

presented EXTRA with every

"ILIXUM" PACKET-3d.

150 picturesque varieties,

INCLUDING OVER 50 UNUSED,

Triangular Fiume, Paraguay, Ivory Coast, Azores, Bosnia, Bulgaria, Malta, Jugo Slavia, Colombia, Gabon, Jamaica, Dahomey, Poland, Morocco, China, Philippines, Hyderabad, St. Pierre, Transvaal, Ukraine, Cape Colony, Mozambique, San Marino, Monaco, etc. Entire Collection for 3d.

Only one packet allowed to each customer.

SEE our PRICE LIST for Bargains in Albums, Sets and Packets.

Errington & Martin, London, E. 9

### FREE!

25 Different—including 5 large Crete, 3 Bosnia, 2 Dutch Indies, large Persia, 8 N.W. Russia, large Hungary, etc., to all genuine approval applicants. Stamplies & Co. (Dept.M.M.), 45, Kitchener Rd., Ipswich.

### EVERY STAMP DIFFERENT

CONDITION FINE

20 Iceland, 1/-; 40 Finland, 9d.; 50 Czecho-Slovakia, 8d.; 50 Georgia and Ukraine, 1/3; 50 Russia, 9d.; 50 Roumania, 9d.; 50 Latvia and Esthonia, 2/-; 50 Austria (only Feldpost issues), 1/9; 40 Airpost, 1/6; 50 Central Lithuania, 1/6; 100 mint Germany Republic, 6d.; 25 Bosnia, 8d. Postage 1½d. extra. C. Faulkner, 90, Woodland Road, London, S.E.19.

12 BARBADOS GRATIS, postage 2d. Collectors Outfits 2/6 and 5/-. Neave, 25, Portnall Road, Paddington, W.9.

## 100 TRIANGULARS & Free!!

We have been able to secure a small supply of a unique "three-cornered" stamp, a block of which we will inc. in each of these free pkts. of 100 diff., which include 40 unused, British Col., War and Armistice Stamps. As supply is limited an early application is advisable. Just request our famous approvals.

LISBURN & TOWNSEND, 201a, London Road, Liverpool.



### Watermarks

N our last issue we described what watermarks are, and how they are imprinted in the paper. We also gave some details of the watermarks of the stamps of Great Britain and promised in this issue to deal with the watermarks of the stamps of some of our Colonies. Before considering these colonial watermarks we may describe a few additional watermarks of the earlier issues of our own stamps that were not mentioned last month.

### A Question of Detail

Many British stamps are identical in




Fig. 5 Large Garters

every respect, except for the watermarks. Some of the more noticeable examples of these differences are as follows: the 1d. red blue with Maltese Crosses in the upper corners, exist (perforated) with watermarks of a small or a large Crown. The 4d. rose of 1855 exists with three watermarks, namely, small, medium Small, Medium and or large Garter. (Fig. 5). Various values of the 1865 set exist water-

marked Emblems or Spray of Rose.

The 5/-, 10/- and £1 stamps of 1867 are

watermarked either with a Maltese Cross or with an Anchor (Fig. 6). The 24d. of 1873 exists watermarked an Anchor or an Orb; while other values of the same year are watermarked Spray of Rose or Imperial Crown. The £1 stamp of 1884 and 1888 appears




Fig. 6 Anchor

with the watermark of either three Imperial Crowns or three Orbs. The King Edward stamps only appeared on one paper, which was watermarked Imperial Crown. The 2/6, 5/- and 10/- values, however, were not printed on this paper, appearing solely on paper watermarked with an Anchor.

### Watermarks of Colonial Stamps

Almost all the British Colonial stamps have been printed either by Messrs.



Fig. 7 Star (Early Colonials)

Perkins, Bacon & Co., or Messrs. De la Rue & Co. The former of these two firms printed the stamps until about 1860, and also printed the earlier stamps of Great Britain. Stamps printed by Messrs. Perkins, Bacon & Co., had a star

Three sizes of this star Zealand stamps (Fig. 8), but in this case the printers were (New Zealand) not Perkins, Bacon & Co.

Messrs. Thomas de la Rue & Co., who printed the stamps after 1860, used many

types of watermarks in printing the stamps. Most of them were formed of one of two designs, namely a Crown over the letters CC, or a Crown over the letters CA (Fig. 9).

The Crown over CC watermarks are now entirely out of date, the letters "CC" being the initials of the words, "Crown Colony." As all the stamps now pass

(Single) through the offices of the Crown Agents, their initials "CA" have been substituted for the earlier "CC." Both the CC and CA watermarks are found in two forms, one being used for stamps of ordinary size and the other for the larger sizes. The size of each individual design itself is the same for both types, but the spacing between the several designs in a whole sheet of stamps is greater for the largersized stamps, so that one design appears in the centre of each stamp.

### Multiple Crown and CA

Fig. 9


Crown

over CA

To save the time wasted by the printer in arranging the paper so that the design of the watermark should appear in the

centre of every stamp a new watermark, the "multiple Crown CA" (Fig. 10), was introduced in 1904. In this type the individual designs are smaller than in the single CA and portions of two, three, or even four designs may appear on each stamp.

WW/



In 1921 still another type of watermark was introduced. This is " multiple known as Script CA" (Fig. 11) in which the "CA" is in Script, while the Crown has been considerably altered. The reason given for this

Fig. 11 Multiple Script CA change is that the old dandy-roll was worn out, and the authorities decided the new one should have a new design. Most of the stamps of the British Colonies have now appeared on this new paper, but a few more have yet to arrive.

### Finding the Watermark

There are three ways of examining a stamp for its watermark. In each case the stamp is looked at from the back so that the printing on the stamp does not obscure the view. The stamp may be held to the light, but the disadvantage of this method is that, although we may be looking at the stamp from the back, the printing on the front shows through so strongly as to prevent the watermark being distinguished.

Another method is to lay the stamp flat, face downwards, on a polished black surface. If this does not avail, a third resort is to pour a little benzine over the

This is sure to show up the waterwithout injuring the stamp. always remember, however, that benzine is a form of petrol and therefore catches fire very easily. It should never bused in a room where there is a naked light or

"Watermark Detectors" are sold by most stamp dealers, and consist of a small tray with a base of black porcelain or marble, and may be helpful in searching for watermarks. The raised edges of the tray prevent the benzine overflowing on to the table, and when benzine is not necessary the black surface shows up the watermark clearly.

#### Errors in Watermarks

In watermarks, as in everything else, there are errors. These usually consist of inverted, reversed, or inverted and reversed watermarks. Inverted watermarks are, as their name implies, upside down. Reversed watermarks mean that the stamps have been printed on the wrong side of the paper. In stamps printed correctly the letters or design of the watermark read backwards when examined from the back of the stamp. This is the same as in the case of printing or writing, when read by looking through the paper from the back. If you should come across a stamp in which the letters read the correct way round, you will have found a specimen with a reversed watermark and its value may be increased.

In addition to the watermark errors mentioned, there are others, including letters omitted, broken letters, wrong watermark, and so on. There is also the error of stamps that should be on watermarked paper being printed on plain paper. These error specimens are very rare and usually bring better prices than

normal specimens.

### RECENT ISSUES

NEWFOUNDLAND. NEW PICTORIAL ISSUE.

We here illustrate three the recently-issued stamps of this enterprising British colony. Issued on 9 July, 1923, the stamps are of different types for each value. They are printed on thick wove paper without watermark, in sheets of 100 perforated



14 or 13½ × 14, by Messrs. Whitehead, Morris & Co., of London. The values are

(omitting 7) and 15, 20 and 24 cents, although the last two values have not yet appeared. Of the CANST REPRESENTATION TO THE PARTY OF THE PAR values illustrated, the 3 cents shows the statue of the Fighting Newfoundlander. This statue was presented to the City of St. John's by Sir Edgar R.

Bowring, in 1922, and was placed in Bowring Park. The 5c. shows "Coast Scenery at

Trinity," and the 8c. "Quidi Vidi Village near St. John's." The set is a handsome one, but the stamps would have been improved if they had been a little


NEWFOUNDLAND

\* NO Ef de 1 1 1 1 1 1 1 1 1 1 1



larger, and it is to be regretted that a view of St. John's itself does not find a place on one of the values.

# Hornby Tank Locos.



This magnificent Tank Loco is a splendid addition to any train system. A glance at the above illustration shows how beautifully this Loco is designed. It is thoroughly representative of the latest type of its class. Measuring 11½ in. in length, it embodies all the characteristics of the Hornby Trains. Suitable for 2 ft. radius rails only.

Beautifully finished in colours; lettered L.M.S and L.N.E.R. Fitted with reversing gear, brake and governor.

Price each ... 32/6

FROM ALL MECCANO DEALERS

# Our Wireless Crystal Set is a Marvel!

(Polished)
Box

Price 10/6 (Royalty) included)

Money returned if not approved.

4,000 ohm Phones. Prices, 12/6, 15/6, 19/6, 25/Copper Aerial Wire - 100 ft., 2/4
List of Wireless Parts Free for Stamp.

### C. LUCAS,


HOBBIES FAMOUS DEPOT, 35, MANCHESTER STREET, LIVERPOOL.

### Bind Your Magazines

This spring-back binder for Meccano Magazines has a strong stiff back, covered with imitation leather, tastefully tooled. It takes a large number of copies and keeps them neat and clean. In black, lettered gold. Price 3/- each (post free).



Meccano Ltd., Binns Road, Liverpool



# What is the first principle of building construction?

IT does not matter how carefully a building is planned or how beautifully it is built; the skill of the finest craftsmen in the world may be lavished on it—all will be in vain unless the foundations are sound.

All over the world there are splendid buildings, which are cracking and collapsing because the foundations are giving way.

You yourself are rather like a building—it does not matter how clever you are with your brains or your hands. It does not matter how strongly you feel you will be able to do great things when you are grown up, unless your foundations are sound, unless you have good health, you will collapse.

Now the very foundation of good health is good teeth—you cannot be really fit and well unless you have sound teeth. Sound teeth are clean teeth.

It is a simple and pleasant matter to keep the teeth in perfect condition by the twice daily use of Gibbs Dentifrice. It cleans and brightens the teeth by removing the greasy food deposits and polishing the millions of tiny waves and facets into which the enamel of a normal tooth is divided.

It is these facets of the enamel (seen only through a powerful magnifying glass) which give the bright, sparkling appearance to clean teeth.

Gibbs Dentifrice is most convenient—a solid cake, protected by an aluminium case—it cannot spill or squeeze out.

Your chemist can supply you with Gibbs Dentifrice at the following prices: Large Size 1/-, De Luxe 1/6, Refills 11d. Popular Size 7½d.

### "The Fortress of Ivory Castles"

FREE! Your little brother or sister will be keenly interested in the Gibbs Fairy Book "THE FORTRESS OF IVORY CASTLES"—a sequel to the famous "Ivory Castle Fairy Book"—an enthralling story comprising 36 beautifully illustrated pages in black and white. Sent free, together with a useful size sample of Gibbs Dentifrice, on receipt of 3d. in stamps to cover cost of packing and postage.

D. & W. GIBBS LTD. (Dept. 78 F.U.), Cold Cream Soap Works, London, E.1.



# MECCANO CHAMPIONSHIP COMPETITION

21 Cups & 460 Medals: total value £250



Model-building Contest has assumed such proportions and has attracted such world-wide interest that we are now able to run it in a form we have long had in mind, and which we think will be greatly appreciated by Meccano model-builders all over the world. For the purpose of this Competition we have divided the various countries into the following groups:—(1) Great Britain. (2) Australasia, South Africa, Canada, India, and all Countries within the British Empire. (3) \*America. (4) \*France, Belgium and Switzerland. (5) \*Scandinavia and Holland. (6) \*Italy. (7) \*Spain and Portugal.

In each of these groups, three Championship Cups will be awarded for the best models submitted, and the winner of each Cup will hold the title of "Meccano Champion" for his particular group and section for twelve months from the date of the awards. The Cups, which have been specially designed for us, are of superb quality, very handsome in appearance, standing over 8-in. in height. Each Cup will be engraved with the name of the winner, and will form a valuable reminder of his prowess and skill. A suitable plinth will be provided with each Cup.

In addition to these special awards, there will be Silver and Bronze Medals in each section and Certificates of Merit to a limited number of other entrants. The total value of the prizes to be awarded will amount to £250.

### Complete List of Awards

SECTION A.—For competitors under 10 years of age on 15th April next. Championship Cup and the title of Meccano Champion for his group and section for the year commencing 1st July next. 20 Silver Medals. 50 Bronze Medals.

SECTION B.—For competitors over 10 years of age and under 14 years of age on 15th April next. Championship Cup and the title of Meccano Champion for his group and section for the year commencing 1st July next. 30 solid Silver Medals. 100 Bronze Medals.

SECTION C.—For competitors over 14 years of age on 15th April next. Championship Cup and the title of Meccano Champion for his group and section for the year commencing 1st July next. 60 solid Silver Medals. 200 Bronze Medals.

In all there will be 110 Silver and 350 Bronze Medals awarded to the competitors in order of merit, and a number of special Certificates of Merit in each section.

(\*Including Colonies).

In making the awards the judges will pay special attention to the following points:-

ORIGINALITY.—Special points will be given to those models showing initiative and originality and which are not simply variations of those illustrated in the Manual of Instructions.

CORRECT CONSTRUCTION.—Models which in their details are constructed on correct mechanical and engineering principles will receive higher marks than those which are built incorrectly or carelessly. No special knowledge is necessary to build models correctly other than that which may be easily acquired from the Meccano Book of Instructions.

GENERAL INTEREST.—Preference will be given to those models which are likely to prove most interesting to Meccano users throughout the world. We shall publish the best models in all civilized countries.

### Meccano Gold Medallist

The competitor who, in the opinion of the Judges, submits the best model in the entire Competition, will be awarded a specially-designed solid Gold Medal, and will be the "Meccano Gold Medallist" for a year. His name and the year in which he gained the title will be engraved on the medal, which will remain his own property.

### CONDITIONS

A competitor may enter any number of models for competition, but only in the section for which he is eligible.

Competitors may be of either sex, and there is no restriction or entrance fee.

Entries must be in the form of Sketches or Photographs, which should show clearly how the model is constructed. Written instructions for building need not be attached unless they are necessary to explain the working of the model. Actual models must not be sent in. The Photographs or the Sketches need not be the work of the competitor.

There is no restriction as to the number of parts that may be used in the construction of a model for the competition.

Each entry must be accompanied by an entry form properly filled in, and the competitor's name and address must appear on each photograph, sketch or sheet of instructions.

The judges will be Meccano Limited, Liverpool, whose decision is final.

No photographs or sketches will be returned to competitors, and no responsibility will be accepted in the event of an entry miscarrying.

Competitors enter on the distinct understanding that the sole copyright of the photos, sketches or models that win prizes, is vested in Meccano Limited.

If considered necessary, winners of prizes may be called upon to furnish proof that they have complied with the conditions.

The latest date for receiving entries from competitors in Great Britain will be 15th April next; from the Colonies 31st May next.

The result of the competition will be announced about June 30th following, or as soon after as possible.

The names of the prize winners will be published in the Meccano Magazine, a copy of which will be sent to all competitors.

No correspondence can be entered into concerning the result of the competition.

Send for your Entry Form to-day. Post Free from Meccano Ltd., Binns Road, Liverpool.



### The Secretary's Notes

am always glad when the dark nights of Winter come, for I know that these are the best months of the year for Meccano boys. Though there are heaps of things to do in the Summer when Cricket and

Happy Members

Tennis are in full swing, to me the Winter always seems to possess greater possibilities. It is during these months that Guild members score, for they are far happier and luckier than the thousands of

other boys to whom the cold dark Winter evenings mean staying indoors, often with nothing at all to do. These boys waste the long evenings week after week, living in hopes of better times when Summer comes again.

But to all Meccano boys, and to Guild members in particular, the dark Winter evenings are the jolliest in the whole year. With a warm cheerful Club Room, with friends around and with the sure knowledge

Joy Night

of a really delightful evening, the Meccano Guild members are the happiest boys in the world. That is the reason why I like the Winter Sessions best, because I know that every Club member is renewing

old friendships as well as making new ones. That he is thoroughly enjoying himself with his chums, and that all are interested in the same things. know, too, that during these months many thousands of new members all over the world will be enrolled and will be able to realise the fine objects of the Guild. The Winter months bring to thousands of boys knowledge of the Meccano Guild, and with it the dawn of a great deal of pleasure and good times in store.

Every boy is not so fortunate as our Guild members, however. Although I do everything in my power to make the Guild known to every Meccano boy, yet every year there are thousands of Meccano boys

Pass It On

who never hear of the Guild. It is up to all you Guild members to bring the Guild before the notice of every Meccano boy and to enrol them one and all as members. Once they see what they are missing

they will not need much persuasion to join. By passing on information about the Guild you will really be doing a good turn to your friends. Now, although the dark nights of Winter are past and we are looking forward to the Summer, I want every member to bear in mind the fact that during the Summer months a great deal of useful work may be done for the Guild. It is during those months, indeed, that plans and arrangements are made for the first Winter Session, and it is during those months also that new recruits should be enrolled. On the cricket field, or out in the open, there are many opportunities for members to bring the Guild to the notice of non-members, and I want you to do this whenever possible during the next six months.

If every Meccano Guild member will enrol just one new member in the Guild we shall have achieved a wonderful record year. To double the membership of the Guild is by no means an impossible task.

A Great Scheme


Already one of the largest brotherhoods of boys, we should become of immense strength. There are few members in the Guild who could not secure one recruit if they tried, during the next two or three months.

It may take perseverance, perhaps, but it could be done, and Meccano boys are well-known for their perseverance and enthusiasm. It is a great scheme and I am going to give it a trial—it is up to you members to help. I am not offering prizes as a reward in this scheme, although I would remind members of the special Recruiting Medallion, full particulars of which will be sent on request. I want each member to ebtain his recruit for the sake of the Guild alone.

## Edinburgh Club's Exhibition

NE of the latest additions to the ranks of our Scottish Clubs is the Boroughmuir Meccano Club, Edinburgh, whose affiliation with the Guild was announced in the last issue of the "M.M." This club possesses a membership of fifty-one, and the Leader is Mr. Donald Maclean, M.A., the Headmaster of the Boroughmuir Secondary School,

A few days previous to affiliation an Exhibition of Meccano models and Hornby Trains was' held in the school, and proved very successful. The room was well decorated with paper festoons and coloured electric globes, and Meccano and Hornby Train posters gave it a very cheerful and inviting appearance. Wireless sets made by the club members were on view, and one of the greatest attractions was a sixty-foot railway track on which a



A section of the recent Exhibition of the Boroughmuir M.C.

Hornby Pullman Train ran at regular ten-minute intervals. Our illustration shows this train alongside a home-made station, and in the background are some very excellent Meccano models, including a Tramcar, Big Wheel, Weighing Machine, and Searchlight Tower, A collection was made and amounted to £2 12s. 6d., half of which sum was given to the Edinburgh Sick Children's Hospital, the remainder being credited to Club Funds.

Meccano Club Leaders No. 11. Cub-Master R. T. J. JOHNSON



Mr. Johnson's Club, "The Ormskirk Wolf-Cub M.C.," is essentially a Scout Club, and well illustrates how successfully a Meccano Club may be combined with Scout activities. The Club was established in October, 1921, at the suggestion of Scoutmaster H. Torr, who still takes an active interest in the Club. Cub-Master Johnson has proved himself to be an enthusiastic and capable Club Leader, as is evidenced by the popularity of both Summer and Winter Sessions.

will gladly send enrolment forms on to any who ask for them, and will help in any way possible either by sending Guild literature or by giving advice. When you have obtained your recruit's signature to the application form for enrolment, write your name on the back of the form and address it to me personally

as I wish to know the names of those members who have helped in this scheme. I hope that this scheme will be so successful that we shall not only make the next Winter Sessions the most famous in the annals of the Guild, but we shall also bring the first object of the Guild nearer to fulfilment "To make every boy's life brighter and happier."

I should like to remind Club Leaders that recommendations for Special Merit Medallions for the Second Winter Session should be sent before the close of the Session. Last Session many recommendations

Second Winter

Session

were made after the Session was ended, with the result that the Medallions were only prepared in February. Complete reports should also be sent in as soon as the last meeting is held, so that I may

know the position of each Club at the end of the Session. Particulars of the activities for the next Session may be sent in at a later date. From the letters that I have received I feel confident that the present Session is far surpassing any yet held. Meccano Clubs all over the country are waking up to what they really can do and there is considerably increased activity in the majority of Clubs. Libraries are being opened; Radio, Photographic and similar sections are being organised; more Exhibitions are being held, and Concerts by Meccano Clubs in aid of deserving causes are becoming regular occurrences. In many cases Clubs within easy distance of each other are combining their activities for various functions. In addition, the usual Club work of model building, lectures, and visits to local places of interest, is being carried on, and the Session will not be long enough by half to accomplish the activities that are planned.

When members fill up the enrolment form for the Correspondence Club and return it to Headquarters I endeavour to find them a suitable correspondent at an early date. Generally I am able to

The Correspondence Club

accommodate them within the next month, but it sometimes happens that this is not possible. For instance, if the request is for a correspondent living in Zululand, who must be a native and able

to understand English, it takes some time to fix this up. If a correspondent is required in Cyprus, St. Helena or in some special town such as Los Angeles. may not be able to find one by return of post. Again, boys who require French correspondents to correspond only in English are likely to have to wait for some time because the majority of French boys wish to either write or receive letters in their own language. It sometimes happens that when boys require correspondents abroad I have to get into touch with our agents in that particular country, hence there is further delay. I am always pleased to enrol boys in the Correspondence Club, however, and in every case I am able to place them in touch with suitable correspondents before any great time elapses. Full particulars of the Correspondence Club will be sent on application.

# How to Run a Successful Meccano Club

by the

Guild Secretary

(Conts nued)

In the case of clubs that have, or are likely to have, a large membership, it is desirable to form a Committee of, say, three or five members in addition to the Leader and Secretary. The boys chosen to serve on the Committee to serve on the Committee should be capable and enthusiastic, for they have more to do than merely attend Committee meetings

and talk.

Although it is not always difficult to start a scheme, it is, as everyone knows, often very difficult to "keep it going." For instance, at the commencement of every year many boys resolve to keep a diary. They purchase a new diary and start the year well by making an entry every day. After a week or so interest dies away, and soon the diary is forgotten. It is the same with many other things in life, including the running of a successful club. It is not the formation of the club that is difficult, but keeping it going week after week, and the necessity for the club officials to give the members a good time at every meeting by arranging an interesting programme. This is one of the reasons why we always insist on affiliated clubs having adult Leaders, for with the greater experience that age brings, it is more often possible to spread the intense enthusiasm of every club member over the whole session, whereas this enthusiasm is often otherwise dissipated in the first two or three meetings.

Next to the Leader the most important work in connection with a Meccano Club remains to be done by the Club Secretary.

The Club to be a Club Secretary.

Secretary The position calls for courage, enthusiasm and perseverance. The boy undertaking this position must be possessed of considerable tact, with a capacity for hard work, which

tact, with a capacity for hard work, which often must be carried out under difficult

circumstances.

To any boys contemplating the formation of a club I would offer this advice:— Do not rush into this work without thought, but if, after due consideration, you honestly believe that you have the necessary qualifications, go ahead. The work is full of interest, and you cannot fail to gain useful experience. At the end of a year or two, you will have the pleasure and honour that comes only to real workers.

The finding of a Leader is seldom a difficult matter, for in every community there are men deeply interested in the welfare of boys; School-Choosing a masters, Sunday-School Teachers, Scoutmasters, or Club Leader sometimes young business men, are always ready to give a helping hand where boys are eager to do some useful work. Usually the secretary of the local Y.M.C.A. will be only too glad to help by finding a suitable Leader. Sometimes the secretary of an already-established boys' club (such as a Scout Club or Boys' Social Club) will introduce a Meccano night. With his guidance and help, the Meccano night may be made

the most interesting night of the week. It should be pointed out to him that although his club has its organisation—a club room, a number of members, and the security that only experience can give—the bargain is not all one-sided, for the Meccano enthusiasts will swell the membership of the established club and will introduce to it many highly-enjoyable, interesting and useful features.

It is, of course, often more satisfactory to have a Meccano Club that is entirely separate from any existing club, as it is then under the complete control of the Leader and Committee. These matters may be arranged, however, when a Club Leader has been chosen, for with him lies the final decision.

(To be continued)

### Special Merit Medallions

RECENT AWARDS.

Special Merit Medallions are awarded each session to the member of each Club who (1) gives the best lecture, and (2) does efficient work for the Club. The Medallions, which are here illustrated, are beautiful both in design and finish.





They have been specially produced by a well-known firm, and on each is engraved the winner's name.

I give below a list of the boys, followed by the names of their Clubs, who have recently been awarded Special Merit Medallions:—

" Meads M.C." Cross, L., " Ethersall M.C." Dewhurst, H., "Holy Trinity and Radio M.C." Dowler, H., "Boston Model Making M.C." Eaton, F., "Rolleston M.C." Fearn, C., "Ormskirk Wolf Cubs." Harrison, S., " Davenport M.C." Helm, E., "Parkstone Congregational M.C." Jacobs, C., " Meads M.C." Laycock, J., " Peterborough M.C.' Marsh, A., "Sparkbrook M.C." Osborne, A., "West View M.C." Plank, F., "Knutsford Lecture Hall M.C." Shepherd, L., Sibley, J., " Luton M.C." "Davenport M.C." Stoker, A. D., "Rolleston M.C." Toon, E. P., "Peterborough M.C." Turney, A., "Dudley M.C." Whitworth, C., " Dudley M.C." Whorton, C.

I hope we shall find that more members have been persuaded to read papers this session.

There is no better training for boys than that they should stand up before their friends and address them in this way. Any subject may be selected (Radio, Engineering, Nature Study and Stamp-Collecting are all good topics), and I am sure that members may count on assistance in the preparation of their papers from their Leaders or parents. After the papers have been read they should be sent to me with the Leader's recommendation, so that I may judge which is the best, and award Special Merit Medallions accordingly.



### E CLUB NOTES G

Meads M.C.—A Model Building Competition was held recently in a local hall and many excellent models were built. Meetings are held every Saturday evening from 8.30 p.m. until 9 p.m., and new members will be welcomed any Club evening. Secretary: Master F. Coombe, Fire Station, 44, Meads Street, Eastbourne.

Wisbech M.C.—The last Session was very successful and terminated with a grand Social, to which parents and friends were invited. The present Session is proving quite as successful, and an Exhibition of models was held in January. The Savings Bank is a popular asset to the Club. Secretary: Master S. Ketteringham, 99, Norwich Road, New Walsoken, Wisbech.

Glenelg (Australia) M.C.—A novel display of models was recently organised by this Club. The display took the form of a river spanned by a swing bridge, over which a Hornby train ran continuously. A steamer sailed on the river, on the banks of which stood a realistic workshop. When the whole was in motion the display won the whole-hearted approval of all the visitors. The new Session commenced on February 6th, with a membership of 26. Secretary: Master F. Squire, 41, Osmond Street, St. Leonards, Glenelg, South Australia.

White Notley M.C.—Club activities during the Session have consisted of model building, lectures, competitions, and exhibitions, and the Club continues to make excellent progress. A Cinematograph Display is to be a special feature of the present Session, and a Lantern Lecture, which is to be given by the Rev. Goodhart, is eagerly anticipated. Secretary: Master F. W. Fox, 2, Station Road, White Notley, nr. Witham, Essex.

Mew Malden M.C.—The Club held a display of models at the beginning of the Session. This was followed by four short lectures given by members of the Club, and later in the evening the Club Leader gave an address on "Hydroplanes." The visitors were very interested in the lectures given by the members, for three of the lecturers were each only nine years of age. Master H. Baker spoke on "The Hornby Clockwork Train," Master V. Smith on "Cranes," and Master Morgan on "The Steam Engine." A fourth lecturer gave a lecture on "Giant Steam Shovels." Secretary: Master E. Alcorn, "Springfield," 7, Poplar Grove, New Malden.

St. Luke's (London, W.18) M.C.—Owing to a number of the boys leaving school, the last Session has not been as successful as those held hitherto. The Club has now been reorganised, however, and good progress is again being made. New members are required, and any boy living in the vicinity should get into touch with the Secretary. Secretary: Master L. Burgess, 166, Wornington Road, North Kensington, London, W.10.

Cobham M.C.—At the close of the first Winter Session a Christmas Party was arranged. This was a great success, and was attended by thirty members, together with their friends. Club activities are proceeding as usual during the present Session. Secretary: Master W. Phillips, Fox & Hounds, Cobham, Surrey.

St. Mary's (Newington Butts) M.C.—This Club is accomplishing useful work among the boys in the vicinity of Newington Butts, S.E.11. In addition to the ordinary work some very interesting lectures have been given by local gentlemen. The Rev. C. R. J. Day gave a lecture on "Ants," while Capt. Kennedy, R.A., delivered a lecture on "Birds." Both were greatly enjoyed by the Club members, as also was the Rev. L. W. Slade's lecture on "Australia." This lecturer brought home the beauty, extensiveness and possibilities of this Colony very vividly to his listeners. A successful Concert was held recently in aid of Club funds, and a Club Magazine is now being issued. Altogether the Club is making considerable headway. Secretary: Mr. C. Curle, 37, Pullens Buildings, Peacock Street, London, S.E.

Melton Mowbray M.C.—All the members are keen and enthusiastic and are doing their utmost to bring new recruits into the Club. In this they receive full encouragement from their capable Leader, Mr. York. A Minstrel Troupe is being organised, as several of the members are interested in work of this kind. Secretary: Master H. White, 25, Bayswater

Peterborough M.C.—This Club held its first Exhibition at the close of the last Session and it was attended with complete success. A very high standard of models was exhibited, including such models as a Workshop with drill, lathe, polishing spindle, illuminated with electric light; a Beam Engine and a Well Borer, both electrically driven; Windmill, Big Wheel, Swing Bridge, Delivery Chute and Tower Lantern. In addition, a realistic railway track was laid out, over which a Zulu Tank Loco and a Hornby No. 1 Goods Train ran during the Exhibition. It is hoped to hold another Exhibition in the near future. Secretary: Master A. Turner, 51, Granville Street Peterborough.

### STAMPS FOR SALE

(See also page 76).

Free to Applicants for Approvals.

Set Large Pict. French Morocco

One of the most beautiful sets ever issued, depicting The Temple at Rabat and Castle Gate at Fez.

Or any one of the following:—

4 French India (surch.). 15 Pict. Œdenburg.
5 Memel on France. 10 White Russia (cat. 3/4).
Ask for particulars of how to increase your collection for nothing.

ALBAN SIMMONS, HILLSIDE, NEW BARNET.

5 Sonora (cat. 2/3).

### FREE! KING'S HEAD PACKET

(containing twelve varieties) to all applicants for my cheap Approval Books. A FURTHER FREE GIFT of a set of mint stamps is sent to purchasers of any of the following 2/6 Packets which I am offering at 1/-each to clear:—German Provisionals, Hungary, Belgium, Bavaria, Austria, War Collection, Holland, France and Sweden.

PERCY DUNBAR, 19a, Barnard Rd., S.W. 11

All different.

7 Pictorial Turkey.

Postage extra.

38 German Provisionals, complete 1/6
50 Jugo Slav. 1/9 | 200 Austria 1/6
50 Czecho-Slov. 1/- | 20 Venezuela 1/20 Montenegro 2/- | 500 all different 2/All the above SETS together ... 10/FREE 50 different POLAND to
Approval Applicants.

PHILIP J. DYKE, 122, Gladstone Rd., Wimbledon

200 different, 1/3; 1,000 different, 6/6; 200 British Colonials, 4/-. Place, Woodhurst, Huntingdon.

SET OF 10 HYDERABAD FREE to appro. applicants. Try my \{\foatsigma}d. Booklets. S. Huckle, 53, Birkenhead Avenue, Kingston-on-Thames.

PAPUA PICTORIAL, HOLLAND PROVISIONAL, Fiume (brig), Zanzibar, Turkestan, Jamaica pictorial, German official, Ceylon, set of 50 unused, etc.; 110 different in all, 3d. if you request approvals (9d. without).

O. HOLLOWAY, 28, HEYBURN ROAD, LIVERPOOL.

5/- Mounted Collection for 1½d. post. Incl., Jamaica (judicial), Paraguay, 4 Prussian offici'ls, Tasmania (pict.). Request approvals. Stammers (M), 51, St. George's Rd., Leyton, E.10.

1000 MIXED STAMPS 1/-, 5000 4/6. Cranwell, 55, Cowslip Road, London, E.18.

Thousands of stamps at \dd. each. Don't pay more. Send p.c. for cheapest approvals in Britain. Exchange with Colonies. Splendid cheap packets. Pollett, 6, Edith Road, London, W.14.

CATAPULTS

Of new and original design. Very accurate. A handy little pocket weapon for Garden, Field, Farm, or Target work, only 1/9 each, postage 3d. (usual price 2/6). Supply ammunition included.

IDEAL NOVELTIES (M. Dept.). Oldchurch Road.

IDEAL NOVELTIES (M. Dept.), Oldchurch Road, Clevedon, SOMERSET. (Money returned if dissatisfied).

Ventriloquist's Instrument, Invisible.
Astonishes. Mystifies. Imitates Birds,
Beasts. Lot 1/- (P.O.) Larger Parcels,
2/-, 5/-.—WONDER CO., Dept. M., 43,
George Street, WESTON-SUPERMARE. (Business by Post only).

AUTOMATIC PEA PISTOL

Loads 15 shots, repeating action, nicely finished, each in box with instructions and supply of ammunition.

No. post free.

1 Black model with nickelled trigger ... 1/3
2 Brightly nickelled throughout ... 1/9

2 Brightly nickelled throughout ... 1/9

Send p.c. for 1924 Catalogue. J. BISHOP & CO., (M),

12, Argyll Place, Regent Street, LONDON, W.1.

A Model Steam Engine

Our readers will be specially interested in the "S.T." steam power plant advertised on page 84, for the engine included in this plant is suitable for driving simple Meccano models. The engine is of the oscillating single-cylinder type. The castings used are of the best gun metal and the boilers are brazed throughout. Incidentally it may be mentioned that one of these boilers tested to destruction did not burst until a pressure of 520 lbs. was reached!

Messrs. Stuart Turner Ltd., the makers, have submitted a specimen Outfit to us and we can testify to the high finish of the parts. The cylinder, piston, cross-head, etc., are beautifully made. It should be noted that the plant is sent out in parts, but the full instructions enable any intelligent boy to assemble these in less than an hour. The engine works very realistically and revolves at a high speed.



EDITORIAL AND ADVERTISING OFFICES:BINNS ROAD, LIVERPOOL.

The "M.M." is published on the 1st of each month and may be ordered from any Meccano dealer, or from any bookstall or newsagent, price 2d. per copy. It will be mailed direct from this office 1/6 for six issues and 3/- for twelve issues (post free).

Small advertisements are inserted in these columns at 1/- per line (average seven words to the line), or 10/- per inch (average 12 lines to the inch). Cash with order.

BINDING CASES to take a large number of copies of the "M.M." are supplied at 3/- each post free. These cases, which have a strong stiff back covered with imitation leather, are lettered in gold and fitted with special spring clip.

Obtaining the "M.M" Overseas

Readers Overseas and in foreign countries may order the *Meccano Magazine* from regular Meccano dealers, or direct from this office. The "M.M." is sold Overseas at 2d. per copy, or mailed (post free) direct from Liverpool, 1/6 for six issues, or 3/- for twelve issues.

IMPORTANT.

Overseas readers are reminded that the prices shown throughout the "M.M." are those relating to the home market. Current Overseas Price Lists of Meccano Products will be mailed free on request to any of the undermentioned agencies. Prices of other goods advertised may be obtained direct from the firms concerned.

CANADA: Meccano Ltd.,

AUSTRALIA: 45, Colborne Street, Toronto.

Messrs. E. G. Page & Co.,

379, Kent Street, Sydney.

NEW ZEALAND: Messrs. Browning Ifwersen Ltd. P.O. Box 129, Auckland.

SOUTH AFRICA: Mr. A. E. Harris, P.O. Box 1199, Johannesburg.

Teacher: "What is 'forced rhubarb'?"


Bobbie (who has had "FORCE" for breakfast every morning): "Please teacher, Rhubarb and 'FORCE"

Yet Bobbie was right - although it was not the answer teacher expected. Bob was thinking of \*FORCE-D" rhubarb, which is a dish he is very fond of.

You would like "FORCE-D" rhubarb because the crispy brown flakes of toasted malted wheat give you something quite different, far nicer than the ordinary stewed rhubarb you have been used to. "FORCE" is such a fine food for health and strength that mother will

not mind at all if you ask her to let you have it regularly. Have "FORCE" for breakfast with hot milk (it needs no cooking), and when you have rhubarb, have "FORCE" too, and find out for yourself how delicious "FORCE-D" rhubarb is.

FREE SAMPLE.—Send your name and address to "Sunny Jim," Dept. A.Y.8, 197, Gt. Portland St., London, W.1., and he will send you a nice trial packet of "FORCE" containing enough for two good meals.



WHOLE WHEAT FLAKES
MALTED AND TOASTED





\ / E give on this page the final puzzles in the competition announced in our January issue. This competition has extended over three issues and is for Guild members only. We would remind our readers that each puzzle is numbered, and that entrants are to write their solutions on a post card alongside the number of the puzzle concerned. Solutions for the final series must be received in this office before the 25th March, on which date the competition will close. On 25th March we shall classify all the entries received, and the winner will be the competitor who has given the greatest number of correct solutions to the three sets of puzzles.

Those who have sent in answers to the previous puzzles should send in their replies to the puzzles on this page, even though their answers to the previous puzzles may not all be correct. It does not follow that the winner will be able to give correct answers to all the puzzles. We have given some real "posers," as we know our readers are far too sharp and clever to be interested in "ordinary"

puzzles!

The first prize will be Meccano Products to the value of £2 2s. 0d. Second and third prizes to the value of £1 1s. 0d. and 10s. 6d. respectively, all to be selected from our current catalogue by the winners.

### March Puzzles

Remember that this Competition runs over three months, and in addition to the puzzles on this page, entrants were required to solve the puzzles in the January and February issues in order to qualify for a prize. This Competition is open to Guild members only, and full particulars in regard to joining the Guild will be sent (post free) on application, to any of our readers who are not already members.

No. 11

What is it that men love more than life, Fear more than death or mortal strife, The poor man has, the rich man wants, The miser spends, the spendthrift saves And all men carry to their graves.

No. 12

The tail of a fish weighs 3 lbs., the head weighs as much as the tail and half the body, and the body weighs as much as the head and tail together. What is the weight of the fish?

No. 13

Mary is 24 years old. Mary is twice as old as Ann was when Mary was as old as Ann is now. What is the age of Ann?

No. 14

The sum of the ages of Mary and Ann is 64 years. Mary is twice as old as Ann was when Mary was half as old as Ann will be when Ann is three times as old as Mary was when Mary was three times as old as Ann. What is the age of each?

No. 1.

A ship with a crew of 175 set sail with sufficient water to last the voyage, but after 30 days an epidemic carried off 3 men daily, and a storm protracted the voyage 3 weeks. The water supply just lasted, however, until she reached her destination. Of how many days was the voyage?

No. 16

A and B travelled on the same road and at the same rate from H to K. At the 50th milestone from K, A overtook a flock of geese proceeding at the rate of 3 miles in 2 hours, and 2 hours afterwards he met a wagon moving at the rate of 9 miles in 4 hours. B overtook the geese at the 45th milestone and met the wagon 40 minutes before he came to the 31st milestone. How far was B from K when A arrived there?

### Answers to Last Month's Puzzles

No. 6

SOLUTION TO THE SHUNTING PUZZLE:

(1) Loco A with 13 wagons, moves forward and then shunts back into siding S, clear of the single line.
(2) The train B then proceeds past the siding, taking A's remaining wagons and itself clear of the siding.
(3) Loco A and its 13 wagons then come out of siding S and advance far enough to allow train B to deposit the remaining wagons of train A in siding S. Train B then proceeds to its destination, while loco A and its 13 wagons return to the siding, pick up their remaining trucks, and then proceed on their journey.

No. 7

Come landlord fill the flowing POTS, Until the TOPS run over, To-night we'll STOP upon this SPOT, To-morrow POST to Dover.

No. 8: Smith.

No. 9

Were "but" but "and," and "and" but "but," "but and and but," but "and and but" but "but and and and," and "but and and and," and "but and and and," and "and and and and" but "but and but."

No. 10: 22 miles.

We offer a prize of 5/- for the best puzzle submitted each month, and prizes of 2/6 each for any other puzzles printed.

Puzzles should be expressed as clearly as possible and the answers should be given in each case. Diagrams should be clearly drawn and letters should be addressed "Puzzles," Meccano Magazine, Binns Road, Liverpool.

Dick: "I say, dad, is oxygen what oxen breathe all day?"

Father: "Of course—and it is also what every other creature breathes."

Dick: "And is nitrogen what everyone breathes

at night?"

\* \* \*

Mr. Brown: "What's the idea of these china dishes

on my wireless set?"

Mrs. Brown: "You ought to be glad I put them there because now you can tell Mr. Jones that you got China on your radio."

"When Jack and I are married, I'm going to have three servants."

"You will probably have twenty-three, my dear—but not all at once."

Aunt Dorothy:
How many Commandments are
there, Johnny?"

Johnny: "Ten."
Aunt Dorothy:
Suppose you were to
break one of them?"

Johnny (hopefully): "Then there'd be nine."

Bribery in the Pantry

Grace: "Oh! Fred, stealing jam! I'm going to tell mother."
Fred: "Wouldn't you rather have some jam?"

It Served Them Right

Minister's Wife: "Wake up! There are burglars in the house."

Minister: "Don't get excited, dear, let them find out their mistake themselves!"

The late Lord Halsbury once visited a certain lunatic asylum in his official capacity.

"I'm the Lord Chancellor," he announced to the attendant at the door.

The man looked at him curiously for a moment.

"This way, sir," he said very firmly.
"We have three more of 'em in here."

"There's a man outside, sir, that wants to see you about a bill you owe him. He wouldn't give his name."

"What does he look like?"

"Well, he looks as though you'd better pay it."

Q: What is the difference between a hairdresser and a sculptor?

A: One curls up and dyes and the other makes faces and busts!

Q: Why is a moth flying near a candle like a farmyard gate?
A: Because if it keeps on it singes its wings!

Inventors are never taken seriously—even Edison made light of his theories!



"Father," said Dick, looking up from his Meccano, "I saw a deaf and dumb beggar in the street this afternoon, and he had an im-

pediment in his speech!"
"Don't talk nonsense!" exclaimed father.

"But he had," insisted Dick; "one of his middle fingers was missing!"

Shopkeeper: "What can I do for you, my boy?"
Boy: "Please, I've called about your advertisement for a man to retail canaries!"

Shopkeeper: "Yes, and do you think you could sell the birds?"

Boy: "Oh no sir! I only want to know how your

Boy: "Oh, no, sir! I only want to know how your canaries lost their tails!"

George: "It's funny that the pupil of the eye never learns anything!"

Harry: "Yes, and it's also curious that the bridge of the nose is never crossed, and that the roof of the mouth is never repaired!"

### Advertisements

(For Rates see page 82)

CINEMA FILMS. 100 ft. 1/- Post Paid. Phillips, 64, Ewart Street, Brighton.

ADVICE, HANDBOOK & CONSULTATION FREE. King, Registered Patent Agent, 146a, Queen Victoria Street, London, E.C.4. 37 years' references.

### MAKE YOUR OWN ELECTRIC LIGHT

These wonderful Dynamos light brilliantly a 4-6 volt lamp, and take very little power to drive. Dynamos 5/-. Post 6d. Special "De Luxe" Model, giving over twice the output, 7/6. Post 6d.



GREENS

(Dept. N.), 85, New Oxford St., London.

### HOW TO BE TALLER

TALL, GRACEFUL. She or he gets attention, respect, and admiration. You can be 2, 3, or more inches taller. Surprise your friends. Send only 11d. stamp. M. M. Edison, 51, Church Street, South Shore, Blackpool.

The Practical Electrician's Pocket Book contains 570 pages of useful text, tables and data simply and clearly worded. Recommended by the Editor of Meccano Magazine. Price 3/4 post free from Rentell, 36, Maiden Lane, Strand, London.

# Reden Cyclometer

FITTED TO YOUR BICYCLE TELLS YOU:-

How far you have been; Distance from one place to another; Service your Tyres give you; Number of Miles to Destination; Distance Travelled, etc.

Makes your Riding doubly interesting. Its accuracy has been endorsed by all the best authorities, and the experience of your

fathers for 26 years. Insist on a Genuine Veeder. See the Name thereon.

> Beware of German Imitations. Made in Two Models: Regular 7/6. Trip 17/6.

Markt & Co. (London) Ltd., 98-100, Clerkenwell Rd., London, E.C.1.

### Is your father alive?

Yes? That's good. That's why you can afford a Meccano Outfit. 165 years ago we began to take care of boys and girls whose fathers were dead-very often mother was dead, too. 7,000 orphans have been saved from poverty, fed, clothed, educated and started in life. 300 are now at our School at Haverstock Hill, dependent upon us for everything. Talk to your father about this. Tell him that our bread bill alone comes to £3 each day. Ask him if he can, and will, help us. Ask yourself too. Perhaps you would like to send something for our large family. Would you? Please reply to Mr. Fred J. Robinson, Sec., 73, Cheapside, London, E.C.2.

### Alexandra Orphanage


(Incorporated as the Orphan Working School and Alexandra Orphanage).

### CUT THIS OUT.

"Meccano" Pen Coupon. Value 3d. Send 5 of these coupons with only 2/9 direct to the Fleet Pen Co., Fleet Street, E.C. 4.

You will receive by return a splendid British 14-ct. Gold Nibbed Fleet Fountain Pen value 10/6 (Fine, Medium, or Broad Nib). If only 1 coupon is sent, the price is 3/9. 3d. less for each extra coupon up to 4 (Pocket Clip 4d.). Satisfaction guaranteed. Your own name gilt letters, either pen 1/- extra.

Lever Self-Filling Model with Safety Cap, 2/- extra.



### S.T. Steam Plant

with double-acting cylinder, 7/16×7/16 in.

Specially designed for driving Meccano Toys. The engine you can build yourself with the aid of a screwdriver. It is perfectly safe and we absolutely guarantee that it will work when you have built it.

> ENGINE PARTS, 5/-Post 3d.

FINISHED BOILER, 76 Post 6d.

COMPLETE PLANT (post free), 13/-

If you want a bigger engine send 6d. for our complete 72 pp. catalogue.

### Stuart Turner Ltd.

ENGINEERS,

HENLEY-ON-THAMES.

A "Supa" Self-Filling Lever Action FOUNTAIN PEN Nickel-Plated.

Post free for 1/- P.O. (Fine, Medium or Broad Nib) E. M. Creasy, The Bazaar, Tregenna Hill, St. Ives, Cornwall.

### CATALOGUES RECEIVED

We have received the following catalogues this month. Should any of our readers write to the firms concerned, they will assist us by mentioning the "Meccano Maga-

A new price list has been sent to us by Mr. A. Kristich (82, Marchmont Street, Russell Square, London, W.C.1), which shows many reasonably-priced stamps and cheap packets. This advertiser carries practically a complete stock of post-Armistice issues of Mint British Colonials, stamps that are a splendid investment, for they never recede in price. Any reader interested in the collection of unused British Colonials will find this price list of great assistance. The list will be sent free on application.

Messrs. Hobbies' Ltd. (Dereham, Norfolk) new catalogue of 200 pages (price 9d. post free), is a comprehensive guide to all branches of fretwork, with a very interesting section devoted to models of locomotives, motor cars, aeroplanes, etc. A large section is devoted to an array of tools of the finest quality that make for neat and accurate working. The catalogue also deals with the art of picture framing, materials, machines, fretsaws, etc., and includes over one hundred pages of designs, ranging from dolls' furniture and simple brackets to handsome china cabinets over 2 ft. in height. Carpenters' and Joiners' Outfits range in price from a simple outfit at 9/6 to an elaborate tool chest price 55/-. Fretwork Outfits range from small sets price 4/- to elegant cabinets price 57/6. The catalogue is beautifully printed on art paper, and is a vade mecum to workers in wood.

### Into the Land of Fun—(cont. from p. 63)


direction or the other. Steering is effected by a 1" pulley wheel fixed on a rod, at the lower end of which is a 1\frac{1}{2}" pulley wheel. A cord wound twice around this pulley is connected to a double angle strip in which the steering axle is journalled.

This Tipping Wagon may be employed with great advantage as an accessory to a Hornby train system, by using it to transport loads from the sidings to some distant point or vice versa.

NEXT MONTH:

SOME USES OF NEW PARTS

### Interesting Railway Publications



\ / E have a very large selection of photographs of Locomotives—ranging from the early examples of Hackworth and Stephenson to the modern mammoths working famous express trains on the British Railways, such as the Cornish Riviera Express, Great Western Railway-Scotch Expresses on the L.M.S. and L. & N.E.R.—Continental Boat Trains, Southern Railway. Sample 8x6 photo of G.W.R. "Caerphilly Castle," L.M. & S. "Croxteth" or L. & N.E.R. "Pacific" sent post free for 1/8.

PHOTOGRAPH CARDS of locomotives forming the four groups-viz., G.W.R., L.M. & S. L. & N.E. and Southern (Four sets)-12 cards in each set, price 3/9 per set post free. COLOURED CARDS-Nine sets of twelve in each, comprising locomotives-trains-stations, etc. Price 1/6 per set post free—or 13/- the complete collection.

PICTURE STAMPS-72 illustrations in colour of locomotives-trains and railway scenes. Price 1/3

SOUVENIR OF GREAT WESTERN LOCOMOTIVES—containing twelve colletype reproductions of modern locomotives—price 2/9 post free. CHART OF LONDON & NORTH EASTERN—Pacific Type Express Locomotive—size 20 × 30—showing all details of construction—price 1/8 post free. List of photographs, slides, etc., sent free.

F. Moore's Railway Photographs, 3, Amen Corner, LONDON, E.C.4

# 3 FAIRYCYCLES TO BE GIVEN AWAY

to Children under 12 years of age

AN EASY COMPETITION

Just write a little story (not exceeding 150 words) telling us what fun you would get out of a Fairycycle if you had one given you.

The 3 Boys or Girls who send in the best description of uses will be given a Fairycycle FREE.

Write on foolscap and insert at the end the name and address of the Toyshop or Store nearest to where you live, which stocks the real Fairycycle, also your own name, address and age.

Be sure the shop stocks the Real FAIRY-CYCLE, you can tell by looking for the Triangular Trademark and the word Fairycycle on the Frame.

The winners will receive their Fairycycles through the Shop they name in their letter as stocking them.

If no Toyshop or Store near you stocks the Fairycycle, then say so and give the name of one or two who should.

Entries must reach us not later than March 10th, 1924.

The decision of Lines Bros. will be final.

Names and addresses of winners will be published in the April issue of Meccano Magazine.

Mark your envelopes 'Fairycycle Competition' and send them to Lines Bros. Ltd., 9, Fore St., London, E.C.

No employee of Lines Bros. may compete.



The

# FAIRYCYCLE

THE CHILDREN'S BICYCLE

Patent No. 169294

Regd.' Design 677489

As illustrated, only

59/6 each

at all good Toyshops and Stores.



As Advertised in the DAILY MAIL and DAILY MIRROR.

Note the Low Centre of Gravity, this makes it safe for the Kiddies.

Insist on these:—Cone Bearing Steering Head, Brake, Freewheel, Adjustable Chain by means of Pedal Bracket (you know how all chains stretch), Reinforced Seat Pillar, Ball-Bearing Rubber Pedals, Mudguards—Back and Front, Highly-plated Fittings.

If you demand the FAIRYCYCLE (Regd. Trade Mark), you will get them, but look for the Triangle Trade Mark and the word FAIRYCYCLE on frame.

"Be particular in this." Insist on seeing the celebrated Trade Mark on the Fairycycle and on all your toys. It is a guarantee of Quality and Value and of British Manufacture.

Also Supplied on Pneumatic Tyred Tangent Spoke B.B. Wheels.

Wholesale only from

LINES BROS. LTD., 9, Fore St., London, E.C.

# 11 Splendid Lines for Our Readers from

### SCOUTING

Campers - Before elsewhere. come to Gamages -it will save you money. The quality, too, is so much better-give us a trial.

Our position as "The World's Premier Store for Boys" enables us to supply your every possible need—no matter what it is, at the lowest prices in the country. So if what you want is not here, just send us a card for details, or better still, come to Holborn and see it on show. At Gamages you'll see more good things in one afternoon than you'd see elsewhere in a year.

THERE IS A

GAMAGECATALOGUE

Every boy wants a pet sooner or later. At Gamages there is a bird or an animal to suit everybodymonkeys, mice, dogs, birds, snakeseverything.

Come and see them.

### Fuller's Block Accumulators

POCKET - MICROSCOPE

CHEMICAL CABINET

This splendid little Pocket Micro-

scope magnifies 50 diameters (2,500)

superficial). Very useful for

by means of the saucer slide,

CHEMISTRY, BOTANY, etc.

Pond water may be examined

and one plain slide on top.

with 3

Post Free.

Price

Wireless

Special offer of ex-Government Stock, but absolutely unused. 2 volt, 40 amp. 10/6 volt, 40 amp. 21/-

6 volt. 40 amp. 31/6 Post 1/6 Boxes to hold 5 of these, fitted with lid and carrying strap.

Each... Postage extra. Five accumulators and box sent post free.

## for every department-sports, Models, Bieveleseverything. Which one do you want? They're POST FREE ON REQUEST

### The Gamage Single Valve BROADCAST RECEIVER



by the addition of ordinary Honeycomb coil. Note the position of the Marconi" R" Valve-the filament, being held vertical, cannot touch grid when sagging takes place. The tuning coil entirely eliminates self-induction and self-capacity effects. TELEand passed by the P.M.G. and the Marconi Company. Accessories extra.



PHONY can be received up to 40 miles. Licensed

### Order this right away boys, to avoid risk of disappointment.

### A splendid article that the

handyman cannot to be without.

# experiments.

CABINETS

No. 1

STATHAM'S

Packed in

strong cardboard

box containing 58

Chemical Tests

and Apparatus.

Price, including

book of

You can also obtain at Gamages a neat box of Chemicals, complete with instructions for performing 50 experiments for only ....

Larger 5/6 Other sizes at prices up to 99/6 Replacements of Chemicals and Apparatus always in Stock. Write for Replacements List Post Free.

### Cards of Drills 7/64, 1/8 /16, 5/64, 3/32, 5/32, 3/16 /16, 3/32, 1/8, 5/32,

3/16, 7/32, 1/4 ... 2/111

Hand Drills to take all drills up to 1 in.

Also a special line of Breast Drills to take up to lin. 14/9



### The Gamage NULITE LAMP

Absolutely the ideal lamp for boys. Fitted with clip at back for fixing to belt and with signalling complete switch, battery and bulb. This splendid lamp is offered at the special

Usually sold at 12/6

#### POCKET TELESCOPE



Here is another splendid little pocket novelty that every boy should have with the bright days approaching. Made of brass, it has FOUR SECTIONS and measures 3/974 ins. extended. Price complete in case Post Free.

instructions. Larger 10/9, 15/9, 22/6,

All-British



#### For the smaller size Magic Lanterns and Cinematographs We are often asked for

ACETYLENE GENERATORS

So compact, it can be carried

something that will give a more intense light than an oil lamp, and we have just brought out a little Acetylene Generator that is ideal for use with these machines. Including Generator, Container, Rubber Tubing, Gas Adjust ments, Price complete

Post Free

You'll get much better results from your cinematograph with this,

### JUVENILE about in the pocket. Gives beautiful pictures. Complete

ELECTRIC MAGIC LANTERN

with lamp. battery and Extra Batteries

74d. each. Extra Lamps 9d. each.

Extra Slides, per box. of 1 doz. ... 10d.

'Winruber' GYM SHOE



sible to have. In black, brown, and white canvas, these are guaranteed to outlast three pairs of the so-called cheap plim-

gym

impregnated with pure rubber, giving the durability of the former with the elasticity of the latter. The shoes may be doubled up in the pocket without fear of the soles cracking. They are extremely light, delightfully cool to wear and they do not draw the feet. Ideal for indoor, outdoor, sports, holiday and general wear. When ordering state colour required,

Postage 6d, extra.

### CONJURING CABINETS

wonderful assortment of startling tricks, complete with

35/- and 42/-

Also cheaper boxes of with Gamages help.



## A. W. GAMAGE LTD., HOLBORN, LONDON, E.C. 1.